

1) LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: Barton		SE ¼ NE ¼ NE ¼	30	T 19 S	R 15 E/W
Distance and direction from nearest town or city street address of well if located within city? Approx. 10½ miles west of Great Bend, KS					
2) WATER WELL OWNER:					
RR#, St. Address, Box # :		Harold Geil Box 265			
City, State, ZIP Code :		Pawnee Rock, KS 67567	Board of Agriculture, Division of Water Resources Application Number: not required		
3) LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4) DEPTH OF COMPLETED WELL: 114 ft. ELEVATION: unknown			
 N W E S		Depth(s) Groundwater Encountered 1. .47 ft. 2. . ft. 3. . ft.			
		Well's Static Water Level .47 ft. below land surface measured on mo/day/yr .3/24/83			
		Pump test data: Well water was not ck'd ft. after . hours pumping . gpm			
		Est. Yield unknown gpm; Well water was . ft. after . hours pumping . gpm			
		Bore Hole Diameter .9 .in. to .114 .ft., and .in. to .ft.			
		WELL WATER TO BE USED AS: 1 Domestic 3 Feedlot 5 Public water supply 8 Air conditioning 11 Injection well 2 Irrigation 4 Industrial 6 Oil field water supply 9 Dewatering 12 Other (Specify below) Was a chemical/bacteriological sample submitted to Department? Yes.....No..XX.... If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes XX No			
5) TYPE OF BLANK CASING USED:		CASING JOINTS: Glued ..XX... Clamped ..			
1 Steel 3 RMP (SR)		6 Asbestos-Cement 9 Other (specify below) Welded ..			
2 PVC 4 ABS		7 Fiberglass Threaded.			
Blank casing diameter .5 .in. to .74 .ft., Dia. .in. to .ft., Dia. .in. to .ft.					
Casing height above land surface .12 .in., weight .2.277 lbs./ft. Wall thickness or gauge No. .2.14					
TYPE OF SCREEN OR PERFORATION MATERIAL:		7 PVC 10 Asbestos-cement			
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify) ..					
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)					
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped 8 Saw cut 11 None (open hole)			
1 Continuous slot 3 Mill slot 6 Wire wrapped 9 Drilled holes					
2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify) ..					
SCREEN-PERFORATED INTERVALS:		From .74 ft. to .114 ft., From . ft. to .ft.			
		From . ft. to .ft., From . ft. to .ft.			
GRAVEL PACK INTERVALS:		From .45 ft. to .114 ft., From . ft. to .ft.			
ANNULAR FILL		From 10 ft. to 41 ft., From . ft. to .ft.			
6) GROUT MATERIAL:		1 Neat cement 2 Cement grout 3 Bentonite 4 Other ..			
Grout Intervals: From .0 ft. to .10 ft., From .41 ft. to .45 ft., From . ft. to .ft.					
What is the nearest source of possible contamination:		10 Livestock pens 14 Abandoned water well			
1 Septic tank 4 Lateral lines 7 Pit privy 11 Fuel storage 15 Oil well/Gas well					
2 Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 16 Other (specify below)					
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage					
Direction from well? North How many feet? 150					
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
0	44	Topsoil & brown clay			
44	55	Real soft black clay			
55	74	Soft gray clay			
74	95	Black clay & green soft sandy clay w/soft sand at 80'			
95	107	Soft green sandy clay			
107	114	Broken limestone and broken sand-stone and clay (Dakota drift)			
7) CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) .3/24/83 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. .185. This Water Well Record was completed on (mo/day/yr) .4/6/83 under the business name of Clarke Well & Eq., Inc. by (signature) [Signature]					
INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send three copies to Kansas Department of Health and Environment, Division of Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.					