


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County <u>McPherson</u>	Fraction <u>SW NE</u> <u>24 1/4 50 1/4 NE 1/4</u>	Section number <u>29</u>	Township number <u>T 19</u>	Range number <u>S R 2</u>	E/W <u>E/W</u>
2. Distance and direction from nearest town or city: <u>1 1/4 W of Galva</u> Street address of well location if in city:				3. Owner of well: <u>OREG THIESEN</u> R.R. or street: <u>BOX 123 GALVA, KANSAS 67443</u> City, state, zip code:			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <u>10</u> in. Completion date <u>9-16-74</u> Well depth <u>65</u> ft. <u>9-16-74</u>			
				7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary			
5. Type and color of material		From		To		8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other	
<u>Top soil</u>		<u>0</u>		<u>3</u>		9. Casing: Material <u>PVC</u> Height: Above or below Threaded ☐ Welded ☒ Surface <u>2 FT</u> in. RMP ☐ PVC ☐ Weight <u>1 1/2</u> lbs./ft. Dia. <u>5</u> in. to <u>6 1/2</u> ft. depth Wall Thickness: inches or Dia. <u>5</u> in. to <u>6 1/2</u> ft. depth gage No. <u>PIC 160</u>	
<u>Clay - Dark</u>		<u>3</u>		<u>9</u>		10. Screen: Manufacturer's name <u>FEARLESS PLASTIC</u> Type <u>PVC</u> Dia. <u>6"</u> Slot/gauze <u>1/8</u> Length <u>20</u> Set between <u>45</u> ft. and <u>65</u> ft. ft. and <u>65</u> ft. Gravel pack? <u>Yes</u> Size range of material <u>1/16"</u>	
<u>Clay - White</u>		<u>9</u>		<u>27</u>		11. Static water level: <u>28</u> ft. below land surface Date <u>9-16-74</u> mo./day/yr.	
<u>Clay - White w/ Lime Rock</u>		<u>27</u>		<u>32</u>		12. Pumping level below land surfaces: <u>45</u> ft. after <u>1</u> hrs. pumping <u>1</u> g.p.m. ft. after <u>1</u> hrs. pumping <u>1</u> g.p.m. Estimated maximum yield <u>7-10</u> g.p.m.	
<u>Lime Stone</u>		<u>32</u>		<u>35</u>		13. Water sample submitted: <u>Yes</u> ☒ No ☐ Date <u>9-16-74</u> mo./day/yr.	
<u>SAND - FINE - Very -</u>		<u>35</u>		<u>45</u>		14. Well head completion: ☐ Pitless adapter <u>Yes</u> ☒ Pitless adapter <u>Yes</u> ☐ Pitless adapter <u>Yes</u> Inches above grade	
<u>Clay - White mixed with</u>		<u>45</u>		<u>41</u>		15. Well grouted? <u>Yes</u> With: <u>Neat cement</u> ☒ Bentonite ☐ Concrete ☐ Depth: From <u>0</u> ft. to <u>10</u> ft.	
<u>SAND - FINE -</u>		<u>61</u>		<u>63</u>		16. Nearest source of possible contamination: ft. <u>600</u> Direction <u>East</u> Type <u>House</u> Well disinfected upon completion? ☒ Yes ☐ No	
<u>Clay - Buff Hard</u>		<u>63</u>		<u>65</u>		17. Pump: ☒ Not installed Manufacturer's name <u>Not installed</u> Model number <u>Not installed</u> HP <u>Not installed</u> Volts <u>Not installed</u> Length of drop pipe <u>Not installed</u> ft. capacity <u>Not installed</u> g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Reciprocating ☐ Jet ☐ Centrifugal ☐ Other	
<u>Clay - Grey Hard</u>		<u>65</u>		<u>74</u>		18. Elevation:	
<u>Cased 65 Ft. Hole</u>						19. Remarks:	
						20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Patricia Ann Davis</u> <u>138</u> Business name <u>INDUSTRIAL TANKS</u> License No. Address <u>W. 1/2 Sec. 10, T. 19, R. 2, E. 1/4</u> Signed <u>W. 1/2 Sec. 10, T. 19, R. 2, E. 1/4</u> Date <u>9-20-74</u> Authorized representative	

