

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

CAB

Bazine

1. Location of well:		County NESS	Fraction S 1/4 NE 1/4 SW 1/4	Section number 7	Township number T 19 S R 21 E/W	Range number 21
2. Distance and direction from nearest town or city: 3/4 mi. south 1/4 mi. east from Bazine Ks. Street address of well location if in city:			3. Owner of well: MANTIN DE WALD R.R. or street: BAZINE, KANSAS 67516 City, state, zip code:			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 8 in. Completion date 5/25/79 Well depth 411 ft.		
				7. <input type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary		
5. Type and color of material		From	To	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input checked="" type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
top		0	3	9. Casing: Material steel Height: Above or below Threaded <input checked="" type="checkbox"/> Welded <input type="checkbox"/> Surface 12 in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight 9 lbs./ft. Dia. 4 1/2 in. to 325 ft. depth Wall Thickness: inches or Dia. 4 1/2 in. to 390 ft. depth gage No. .219		
yellow clay		3	22	10. Screen: Manufacturer's name same pipe as above slotted with Type band saw Dia. 4 1/2 Slot/gauze 1/16 Length 40 Set between 325 ft. and 345 ft. 491 ft. and 411 ft.		
limestone rock		22	27	Gravel pack? yes Size range of material #1		
black shale		27	126	11. Static water level: 90 ft. below land surface Date 10/18/78 mo./day/yr.		
shell rock and shale some fine hard sandstone		126	190	12. Pumping level below land surfaces: 109 ft. after 48 hrs. pumping 12 g.p.m. ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield 100 plus?? g.p.m.		
multi colored clays and shales		190	320	13. Water sample submitted: _____ mo./day/yr. Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Date _____		
sandstone extremely hard and tight		320	340	14. Well head completion: <input checked="" type="checkbox"/> Pitless adapter 12 Inches above grade		
multi colored clays shales and rock (hard)		340	390	15. Well grouted? yes With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From -4 ft. to -30 ft.		
strips of good fast drilling sandstone		390	410	16. Nearest source of possible contamination: abandoned ft. 60 Direction north Type oil well Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
hard blue-gray shale		410	426	17. Pump: _____ Not installed Manufacturer's name REDA Model number 12D9P071 HP 3/4 Volts 230 Length of drop pipe 126 ft. capacity 9 g.p.m. Type: <input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Dean Waterhouse Drilling 243 Business name License No. _____ Address HANSTON, KANSAS Signed Dean Waterhouse Date 5/25/79 Authorized representative		
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley		2180 21 Rock 27'		<div style="position: absolute; right: 0; top: 50%; transform: translateY(-50%); font-size: 2em;">19 210 7</div> <div style="position: absolute; right: 0; bottom: 0; font-size: 1.5em;">CUESW</div>		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5