

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: NESS NE 1/4 NE 1/4 NW 1/4 29 T 19 S R 24 W

Distance and direction from nearest town or city street address of well if located within city?
 NESS CITY WEST ON HIGHWAY 46, 4 S ON RD N, 4 N & 1/2 WEST

2 WATER WELL OWNER: MILLIES, DAVE
 RR#, St. Address, Box #: 702 JAMES Board of Agriculture, Division of Water Resources
 City, State, ZIP code : NESS CITY, KS 67560- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

/ \	NW	NE
1	NW	NE
N	W	E
1	SW	SE
e	SW	SE
\ /	SW	SE

4 DEPTH OF COMPLETED WELL 425 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 137 ft. below land surface measured on mo/day/yr 03/21/06
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 70 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 10 in. to 425 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: DOMESTIC

Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: CERTA LOC CASIN CASING JOINTS: CERTA-LOC
 Blank casing diameter 5 in. to 425 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21 17
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 280 ft. to 320 ft., From 0 ft. to 0 ft.
 From 360 ft. to 420 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 90 ft., From 0 ft. to 0 ft.
 From 100 ft. to 425 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 5 ft. to 25 ft., From 90 ft. to 100 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: ABANDONED WELL
 Direction from well? WEST How many feet? 30

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	01 TOPSOIL 05 CLAY 02 FINE SAND			
20	40	32 TAN CLAY 36 BLUE CLAY			
40	220	07 BLUE SHALE			
220	240	07 BLUE SHALE 29 SANDSTONE 19 LAYERS			
240	320	29 SANDSTONE			
320	340	29 SANDSTONE 17 CLAY LAYERS			
340	425	29 SANDSTONE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/23/06 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 03/29/06 under the business name of JOB'S WELL SERVICE, INC. by (signature) *Jessie Ciel*