

102½ N. SANTA FE
PHONE 2717

L A T T A A N D F E N T

SALINA, KANSAS
Box 720

WATER WELLS
TEST HOLES

LOG OF WELL

NAME David Bengtson HOLE NO. 1 DATE DRILLED 9-20-50
LOCATION NE ¼ sec. 13 T 19S., R 3E., McPherson CO.
At east side of house.
TYPE OF WELL Domestic TOPOGRAPHY _____
DEPTH 50 FEET. DIAM. OF HOLE 7½ INCHES. DEPTH TO WATER 21.5 FEET Below L. S.
CASINGS DIAM. 5 INCHES. SET AT 50 FEET. FINISH Gravel packed, closed end
YIELD Bailed 5 gallons per minute with water level at 42 feet.
REMARKS Water very bitter, probably oil field brine contamination

DESCRIPTION OF MATERIAL	THICKNESS (FEET)	DEPTH (FEET)	DRILLING CHARACTER & REMARKS
Silt and clay, dark gray, light gray and buff.	9	9	Slow, smooth
Silt and clay, light gray; contains much sand, fine to medium, partly interbedded.	13	22	Fairly slow, occasional chatter on caliche 18-20.
Silt and clay, light gray and buff; contains much sand, fine to medium and some caliche.	17	39	Fairly slow, occasional slight chatter.
Sand, fine to medium, little sand coarse and gravel, fine and silt, buff and light gray, partly cemented	10	49	Fairly fast, chatter
Silt, light gray and tan, interbedded with sand, medium to fine.	7	56	Fairly slow, slight chatter.
Silt and clay, light gray and tan contains much sand, fine.	4	60	Slow, slight chatter