

PETERSON IRRIGATION, INC.

330 HARRISON

PHONE 913-227-3520

LINDSBORG, KANSAS 67456

WATER WELL RECORD

DRILLERS LOG OF WELL

FROM (FT.)	TO (FT.)	KIND OF MATERIAL, COLOR, ETC. (NOTE WATER ZONES, AMOUNT, QUALITY)
0	5	Top Soil
5	9	Buff Clay
9	18	RED Clay
18	25	BROWN Clay & LOOSE LIME ROCK
25	42	FINE SAND
42	49	BROWN Clay (Soft)
49	65	FINE to MED. SAND
65	74	MED. SAND
74	86	Buff Clay
86	90	FINE SAND & GREEN CLAY
90	98	FINE SAND
98	118	MED. SAND
118	122	BLUE SAND
122	165	MEDIUM (EQUIV.) SAND
165	171	MEDIUM COARSE SAND
171	172	GREEN & RED SHALE
		Cased 172 ft
		Cased \$24.00 per ft.
		Well SITE

Well Owner LELAND NICKELLAddress R.R. #1 MOUNDRIAGE, KS.


Drilling Contractor _____

Date Drilled JUNE 1, 1979Method of Drilling REVERSE ROTARY
(Cable tool, rotary, reverse rotary, etc.)Casing Schedule 16" TRANSITE 120 ft
(Amount, Size, Setting—New, Used—Steel, Galv.—Gage or Weight)
From 0 to 120 ftScreen Data (if any): 16" TRANSITE 52 ft
(Length, Diameter, Slot Size, Setting)
From 120 to 172 ftMeasured depth to water on completed well (Static Level) is
40'6" ft. below LAND SURFACE
(Land Surface, Top of Casing, Etc.)TESTED YIELD: _____ gallons per _____ (Min., Hour)
as determined by Est. 1200-1500 gpm
(Bailing, Test Pumping, Etc.)

DRAWDOWN: _____ ft. after _____ hrs.

pumping at _____ gal. per minute.

REMARKS:

LOCATION OF WELL Topographic Sheet _____
[Show location in Section Plat] Elev. _____

NE x SW x Sec. 33
R. 19 S., R. 3 W.
 County McPherson

*Drilled
6-4-79
#1 9275*