

J. P. Kaufman. SE₁ SE₁ Sec. 36, T.19S., R.3W.,
McPherson County

2(Test Hole)

Valley flat.

Drilled November 13, 1947. Depth to water level, 7 feet below land surface.

Soil, gray	5	5	
Sand, fine to coarse, and silt, dark gray to black	3	8	Fast
Silt and clay; gray	5	13	
Silt, sandy, gray	3	16	
Sand and gravel, fine to medium; gray- tan; contains little coarse gravel	2	18	Fast
Clay and silt; light green-gray and pink-brown; caliche	8	26	Slow
Silt and clay; red-brown; contains caliche nodules	16	42	Little faster
Clay and silt; sandy; gray-pink and pink- brown	10	52	Slower
Silt, clay, and caliche; light gray	4	56	Faster
PERMIAN - SELWINGTON FORMATION Shale, green	1	57	Slow

November 19: Completed 6-inch gravel-packed well to 19 feet, lower 3 feet per-
forated. Yield, 2-3 gallons a minute.