

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
County: McPherson	NW ¼ NE ¼ SE ¼	29	T 19 S	R 3 EW

Distance and direction from nearest town or city street address of well if located within city?

115 W. Kansas, McPherson

2 WATER WELL OWNER: Green Lantern	Board of Agriculture, Division of Water Resources
RP#, St. Address, Box # : PO Box 856	Application Number:
City, State, ZIP Code : Salina, KS 67402	

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL: 120 ft. ELEVATION:
	Depth(s) Groundwater Encountered 1. ft 2. ft 3. ft WELL'S STATIC WATER LEVEL 96.51 ft. below land surface measured on mo/day/yr 7/14/2014 Pump test data: Well water was NA ft. after hours pumping gpm Est. Yield NA gpm: Well water was ft. after hours pumping gpm Bore Hole Diameter 8 in. to 122 ft. and in. to ft. WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well Was a chemical/bacteriological sample submitted to Department? Yes.....No ☒ ; If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes No ☒

5 TYPE OF BLANK CASING USED:	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued Clamped
1 Steel	3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below) Welded
2 PVC	4 ABS	7 Fiberglass	Threaded. ☒
Blank casing diameter 4 in. to 90 ft. Dia. in. to ft. Dia. in. to ft.			
Casing height above land surface in., weight lbs./ft. Wall thickness or gauge No. Sch. 40			
TYPE OF SCREEN OR PERFORATION MATERIAL	7 PVC	10 Asbestos-cement	
1 Steel	3 Stainless steel	5 Fiberglass	8 RMP (SR)
2 Brass	4 Galvanized steel	6 Concrete tile	9 ABS
SCREEN OR PERFORATION OPENINGS ARE:	5 Gauzed wrapped	8 Saw cut	11 None (open hole)
1 Continuous slot	3 Mill slot	6 Wire wrapped	9 Drilled holes
2 Louvered shutter	4 Key punched	7 Torch cut	10 Other (specify)
SCREEN-PERFORATED INTERVALS: From 90 ft. to 120 ft. From ft. to ft.			
GRAVEL PACK INTERVALS: From 85 ft. to 122 ft. From ft. to ft.			

6 GROUT MATERIAL:	1 Neat cement	2 Cement grout	3 Bentonite	4 Other Concrete
Grout intervals: From 0 ft. to 2 ft. From 2 ft. to 85 ft. From ft. to ft.				
What is the nearest source of possible contamination:	1 Septic tank	4 Lateral lines	7 Pit privy	10 Livestock pens
	2 Sewer lines	5 Cess pool	8 Sewage lagoon	11 Fuel storage
	3 Watertight sewer lines	6 Seepage pit	9 Feedyard	12 Fertilizer storage
Direction from well?				13 Insecticide storage
				14 Abandoned water well
				15 Oil well/Gas well
				16 Other (specify below)
				How many feet?

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	Concrete,			
1	3	Topsoil, Black			
3	20	Clay, Red Brown			
20	40	Clay, silty, firm, Brown			
40	50	Clay, silty, firm, Brown to Tan			
50	70	Clay, Gray			
70	75	Clay, Gray to Tan			
75	85	Clay, sandy (m-c), Brown			
85	100	Sand, m, clayey, Brown			
100	105	Clay, Tan			
105	110	Clay, some sand, Tan			
110	120	Sand, m-c, Brown to Tan			
					MW15, Flushmount

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 6/30/2014 and this record is true to the best of my knowledge and belief.
Kansas Water Well Contractor's License No. 527 This Water Well Record was completed on (mo/day/yr) 7/6/14
under the business name of GeoCore, Inc. by (signature) <i>Dan Roll</i>

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.