


1 LOCATION OF WATER WELL: Fraction SE 1/4 NE 1/4 NE 1/4 Section Number 29 Township Number T 19 S Range Number R 3 E
 County: McPherson
 Distance and direction from nearest town or city street address of well if located within city?
519 N. Main McPherson, KS

2 WATER WELL OWNER: City of McPherson
 RR#, St. Address, Box #: 400 E. Kansas A.H.N. V. Dossert
 City, State, ZIP Code McPherson, KS 67460
 Board of Agriculture, Division of Water Resources
 Application Number: —

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

 4 DEPTH OF COMPLETED WELL: 103 ft. ELEVATION: — ft.
 Depth(s) Groundwater Encountered 1. 80 ft. 2. — ft. 3. — ft.
 WELL'S STATIC WATER LEVEL 84.05 ft. below land surface measured on 12-14-95
 Pump test data: Well water was — ft. after — hours pumping — gpm
 Est. Yield — gpm: Well water was — ft. after — hours pumping — gpm
 Bore Hole Diameter 8.625 in. to 103 ft., and — in. to — ft.
 WELL WATER TO BE USED AS:
 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)
 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well mw-4
 Was a chemical/bacteriological sample submitted to Department? Yes — No X; If yes, mo/day/yr sample was submitted —
 Water Well Disinfected? Yes — No X

5 TYPE OF BLANK CASING USED:
 1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued — Clamped —
2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded —
 7 Fiberglass Threaded X
 Blank casing diameter 2 in. to 7.4 ft. Dia — in. to — ft. Dia — in. to — ft.
 Casing height above land surface 0 in., weight Sch 40 lbs./ft. Wall thickness or gauge No. —
 TYPE OF SCREEN OR PERFORATION MATERIAL:
 1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 10 Asbestos-cement
 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)
 SCREEN OR PERFORATION OPENINGS ARE:
 1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole)
 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes
 7 Torch cut 10 Other (specify) —
 SCREEN-PERFORATED INTERVALS: From 74 ft. to 99 ft. From — ft. to — ft.
 From — ft. to — ft. From — ft. to — ft.
 SAND — ft. to — ft. From — ft. to — ft.
 GRAVEL PACK INTERVALS: From 72 ft. to 99 ft. From — ft. to — ft.
 From — ft. to — ft. From — ft. to — ft.

6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other —
 Grout Intervals: From 0 ft. to 70 ft. From 70 ft. to 72 ft. From — ft. to — ft.
 What is the nearest source of possible contamination:
 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well
 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well
 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below) contaminated site
 13 Insecticide storage
 Direction from well? — How many feet? —

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	0.5'	Concrete			
0.5	2.5	Clayey silt			
2.5	16.0	Silty clay			
16.0	28.0	Clayey silt			
28.0	36.0	Silty clay			
36.0	51.0	Silty clay			
51.0	53.0	Clay			
53.0	65.0	Clayey silt			
65.0	103.0	SAND			
103.0	TD	END of Borehole			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 12-12-94 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 585 This Water Well Record was completed on (mo/day/yr) 12/30/94
 under the business name of Associated Environmental, Inc by (signature) P. Taylor