

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 086 SCOTT SE 1/4 NW 1/4 NE 1/4 36 T 19 S R 33 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 1/4 MILE SOUTH OF SHALLOW WATER

2 WATER WELL OWNER: EDNA COLLINGWOOD TRUST
 RR#, St. Address, Box #: P.O. BOX 1184 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: HUTCHINSON, KS 67504- Application Number: SC087

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 205 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 95 ft. below land surface measured on mo/day/yr 02/05/94
 Pump test data: Well water was 113 ft. after 4 hours pumping 618 gpm
 Estimated Yield 650 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 205 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? No

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 205 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 100 ft. to 140 ft., From 175 ft. to 185 ft.
 From 150 ft. to 170 ft., From 193 ft. to 203 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 205 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? WEST How many feet? 50

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	19	01 CLAY 02 SILT			
19	25	07 FINE SAND 09 COARSE SAND 13 FINE GRAVEL			
25	44	01 CLAY 05 SAND			
44	58	07 FINE SAND 09 COARSE SAND 14 MED GRAVEL			
58	83	01 CLAY 07 FINE SAND			
83	106	07 FINE SAND 09 COARSE SAND 13 FINE GRAVEL			
106	124	01 CLAY			
124	130	07 FINE SAND 09 COARSE SAND 13 FINE GRAVEL			
130	134	01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 02/02/94 and this record is true to the best of my knowledge and belief, Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/05/94
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

