

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

19 4W 2PWSWSE
T R EW sec 1/4 1/4 1/4 No.

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

SW 2 Acres

1 Location of well: County <u>McPherson</u> Township name <u>Jackson</u> Fraction <u>SW 1/4 SE 1/4</u> Section number <u>2</u> Town number <u>T-19-S</u> Range number <u>R-4-W</u>	
Distance and direction from nearest town or city: <u>2 N - 4 1/2 W</u>	
Street address of well location if in city: <u>McPherson</u>	
3 Owner of well: <u>Bob Allen</u> Address: <u>R.R. 3 McPherson Kan 67460</u>	
Locate with "X" in section below: Sketch map:	
2 Type and color of material	
From To	
<u>Top Soil</u> 0 4	
<u>Dark Clay</u> 4 6	
<u>Benck Clay</u> 6 14	
<u>Yellow Clay</u> 14 42	
<u>Grey Clay</u> 42 53	
<u>Black Clay</u> 53 56	
<u>Med sand & gravel - loose - Dry</u> 56 60	
<u>Grey green clay</u> 60 66	
<u>Med sand & gravel - loose - Dry</u> 66 95	
<u>Equal sand & fine to med (Iron)</u> 95 116	
<u>Yellow Clay</u> 116 119	
<u>Equal sand Med - Very little Iron.</u> 119 135	
(use a second sheet if needed)	
16 Remarks: elevation	
Topography: <u>Flat land.</u>	
<input type="checkbox"/> Hill	
<input type="checkbox"/> Slope	
<input checked="" type="checkbox"/> Upland	
<input type="checkbox"/> Valley	
4 Well depth: <u>132</u> ft. Date of completion: <u>10-9-75</u>	
Well diameter: <u>8</u> in.	
5 <input type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug	
<input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary	
6 Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry	
<input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Commercial	
<input type="checkbox"/> Test well <input type="checkbox"/>	
7 Casing: Material <u>PVC</u> Height: <u>above</u> below	
Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <u>12</u> in.	
Diam. <u>5</u> in. to <u>132</u> ft. depth Weight <u>132</u> lbs./ft.	
Drive shoe? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
8 Screen: Manufacturer <u>Bentonite</u>	
Type <u>PVC</u> Dia. <u>5</u> in.	
Slot gauge <u>432</u> Length <u>10 ft</u>	
Set between <u>122</u> ft. and <u>132</u> ft.	
Fittings: <u>1 1/2 - 1 1/2</u>	
Gravel pack <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Size range of material <u>1/8 - 1/4</u>	
9 Static water level: <u>92</u> ft. below land surface Date <u>10-9-75</u>	
10 Pumping level below land surfaces: <u>95</u> ft. after <u>2</u> hrs. pumping <u>15</u> g.p.m.	
<u>ft.</u> after <u>hrs.</u> pumping <u>g.p.m.</u>	
Estimated maximum yield <u>50</u> g.p.m.	
11 Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <u>10-9-75</u>	
12 Well head completion: <u>12</u> in.	
<input checked="" type="checkbox"/> Pitless adapter <input type="checkbox"/> Inches above grade	
13 Well grouted? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	
<input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/>	
Depth: From <u>0</u> ft. to <u>15</u> ft.	
14 Nearest source of possible contamination: <u>Septic</u>	
ft. <u>75</u> Direction <u>S.E.</u> Type <u>Septic</u>	
Well disinfected upon completion? <input type="checkbox"/> Yes <input type="checkbox"/> No	
15 Pump: <input checked="" type="checkbox"/> Not installed	
Manufacturer's name <u>138</u>	
Model number <u>150</u> HP <u>150</u> Volts <u>150</u>	
Length of drop pipe <u>ft.</u> capacity <u>g.m.p.</u>	
Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine	
<input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating	
<input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.	
<u>Arthur Brown</u> <u>138</u>	
Business name <u>150</u> License No. <u>150</u>	
Address <u>150</u>	
Signed <u>150</u> Date <u>10-9-75</u>	
Authorized representative	