

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

T R EW sec 1/4 1/4 1/4 No.

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

1 Location of well:	County McPHERSON	Township name JACKSON	Fraction NE 1/4	Section number 14	Town number T-19-S	Range number R-4-W
Distance and direction from nearest town or city: 2 N. 3 1/2 WEST				3 Owner of well: BILL KUBIN		
Street address of well location if in city: McPHERSON				Address: RR McPHERSON, KANSAS		
Locate with "X" in section below:		Sketch map:		4 Well depth: 219 ft. Date of completion 9-22-75 Well diameter 30 in.		
				5 ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
				6 Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Commercial ☐ Test well ☐		
				7 Casing: Material TRANSITE Height: above/below Threaded ☐ Welded ☐ Surface ☐ in. Diam. 16 in. to 219 ft. depth Drive shoe? ☐ Yes ☒ No Weight 28 lbs./ft.		
				8 Screen: Manufacturer AURORA TILE CO Type TRANSITE Dia. 16" I.D. Slot/gauze 3/32 Length 52 ft. Set between 169 ft. and 219 ft. Fittings: Gravel pack ☒ Yes ☐ No Size range of material 4"		
2 Type and color of material				9 Static water level: 95 ft. below land surface Date 9-22-75		
				10 Pumping level below land surfaces: ____ ft. after ____ hrs. pumping ____ g.p.m. ____ ft. after ____ hrs. pumping ____ g.p.m. Estimated maximum yield 1500 g.p.m.		
Top SOIL - BLACK BUFF CLAY (PINK) CLAY - RED SAND + GRAVEL - DRY Good Water LOSS - FINE SANDS CLAY - (WHITE) Water Loss - FINE SANDS SAND - FINE CLAY - WHITE Water Loss - FINE SANDS BUFF CLAY - HARD - Water Loss - SAND + GRAVEL Red SHALE				11 Water sample submitted: ☐ Yes ☒ No Date ____		
				12 Well head completion: ☐ Pitless adapter ☒ 12 Inches above grade		
(use a second sheet if needed)				13 Well grouted? ☒ Yes ☐ No ☐ Neat cement ☐ Bentonite ☒ Puddle clay Depth: From 0 ft. to 15 ft.		
				14 Nearest source of possible contamination: ft. SW Direction NO Type Red dirt Well disinfected upon completion? ☐ Yes ☒ No		
16 Remarks: elevation ON FLAT LAND				15 Pump: ☒ Not installed Manufacturer's name WESTERN LAND ROLLER Model number 8M HP 60 Volts ____ Length of drop pipe 150 ft. capacity 150 g.m.p. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
				17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. PETERSON BOOS INC License No. 138 Address Box 150 LINASARC KS Signed Will Peterson Date 9-23-75 Authorized representative		