

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
County: McPherson	SW ¼ NW ¼ NW ¼	25	T 19 S	R 4

Distance and direction from nearest town or city street address of well if located within city?

2 miles West of McPherson

2 WATER WELL OWNER: Anson Dossett	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # : Rt 2	Application Number:
City, State, ZIP Code : McPherson, KS 67460	

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL: 192 ft. ELEVATION:
	Depth(s) Groundwater Encountered 1... 90... ft. 2... ft. 3... ft. WELL'S STATIC WATER LEVEL 90... ft. below land surface measured on mo/day/yr 12-7-93 Pump test data: Well water was ... ft. after ... hours pumping ... gpm Est. Yield 40-50 gpm: Well water was ... ft. after ... hours pumping ... gpm Bore Hole Diameter 8... in. to 193... ft., and ... in. to ... ft. WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well Was a chemical/bacteriological sample submitted to Department? Yes... No. X...; If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes X No

5 TYPE OF BLANK CASING USED:	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued X Clamped
1 Steel	3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below)
2 PVC	4 ABS	7 Fiberglass	10 Asbestos-cement
Blank casing diameter 5... in. to 182... ft., Dia			11 Other (specify)
Casing height above land surface 12... in., weight 2.37... lbs./ft. Wall thickness or gauge No. 21.4			12 None used (open hole)
TYPE OF SCREEN OR PERFORATION MATERIAL:	5 Fiberglass	8 RMP (SR)	
1 Steel	3 Stainless steel	9 ABS	
2 Brass	4 Galvanized steel	6 Concrete tile	
SCREEN OR PERFORATION OPENINGS ARE:	5 Gauzed wrapped	8 Saw cut	11 None (open hole)
1 Continuous slot	3 Mill slot	6 Wire wrapped	9 Drilled holes
2 Louvered shutter	4 Key punched	7 Torch cut	10 Other (specify)
SCREEN-PERFORATED INTERVALS:	From 182... ft. to 192... ft.		
	From ... ft. to ... ft.		
GRAVEL PACK INTERVALS:	From 25... ft. to 192... ft.		
	From ... ft. to ... ft.		

6 GROUT MATERIAL:	1 Neat cement	2 Cement grout	3 Bentonite	4 Other
GROUT INTERVALS:	From 5... ft. to 25... ft.			
What is the nearest source of possible contamination:				
1 Septic tank	4 Lateral lines	7 Pit privy	10 Livestock pens	14 Abandoned water well
2 Sewer lines	5 Cess pool	8 Sewage lagoon	11 Fuel storage	15 Oil well/Gas well
3 Watertight sewer lines	6 Seepage pit	9 Feedyard	12 Fertilizer storage	16 Other (specify below)
Direction from well? East				
			How many feet? 75ft	

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	3	Top Soil			
3	12	Gray Clay			
12	16	Brown Clay			
16	38	Tan Clay			
38	41	Fine Sand			
41	46	Silty Tan Clays			
46	61	Fine Silty Sand			
61	64	Tan Clays			
64	81	Fine Sands			
81	83	Tan Clay			
83	100	Gray Sand			
100	104	Gray Clay			
104	116	Gray Sand			
116	118	Brown Clay			
118	193	Light Brown Sands			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 12-7-93 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 138 This Water Well Record was completed on (mo/day/yr) 12-9-93 under the business name of Peterson Irrigation Inc. by (signature) Mike Peterson
--