

Includes holes in

Sections: 6, 7, 8, 17, 20, 21

✓ ~~A~~
Windom City

1

1-16-50

NW cor. sec. 21

19S.

5W

McPherson

Just west of abandoned well. ?

test hole

raving slope

33.5

5

14.3

2 gallons per minute-bailer test

Soil, dark gray.

1.5

1.5 Fast, smooth

Clay, gray to yellow-gray.

4

5.5 Slow, smooth

Iowa Shale:

(Marquette member)

Sandstone, medium to fine, white and yellow, interbedded with clay yellow and light gray.

3

8.5 Slow, alternating chatter and smooth

Sandstone, fine to medium, yellow and white, interbedded with little clay, gray and yellow.

8.5

17 Fairly fast, slight chatter.

Clay, yellow-gray grading downward to blue-gray.

11

28 Slow, smooth

Shale, blue-gray; contains few thin siltstone zones.

5

33 Very slow, smooth

Windom member:

Chiquina limestone.

0.5

33.5 Very slow, chatter