

✓ Lindell Geiman owner

H Y D R A U L I C D R I L L I N G C O M P A N Y

216 E. PACIFIC
PHONE 7-1532
NIGHT PHONE 6692

SALINA, KANSAS
Box 477

LOG OF WELL

NAME Lindell Geiman HOLE NO. 1 DATE DRILLED 2-9-53
LOCATION Highway 30 T 12S, R 5W, McPherson Co.
100' west of barn
TYPE OF WELL stock TOPOGRAPHY hill
DEPTH 60 FEET. DIAM. OF HOLE 6 INCHES. DEPTH TO WATER 40 FEET
CASINGS: 60' 4" galv., bottom 2.5' perforated, open end
YIELD Failed at 2 gallons per minute
REMARKS _____

DESCRIPTION OF MATERIAL	THICKNESS (FEET)	DEPTH (FEET)	DRILLING CHARACTER & REMARKS
Top soil, silty, tan to gray	2	2	
Silt and clay, soft, tan to gray	4.5	6.5	
Silt and clay, soft, tan. Contains caliche below 9.5	5	11.5	
Clay, soft, gray-green with yellow- brown zones	19.5	31	
Silt, clayey, soft, red, purple, gray-green and yellow-tan	4	35	
Silt, clayey, soft, light gray to cream	3	38	
Clay, silty, soft, red, purple, cream	9.5	47.5	
Sandstone, very fine to fine, poorly cemented and interbedded clay, silty	1.5	49	
Clay, silty, fairly soft, dark red with green and yellow-tan zones	11	60	