

## **WATER WELL RECORD**

## Form WWC-5

## Division of Water Resources App. No.

**7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION:** This water well was  constructed,  reconstructed, or  plugged under my jurisdiction and was completed on (mo/day/year) 9/24/09 ..... and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 433 ..... This Water Well Record was completed on (mo/day/year) 12/10/09 ..... under the business name of Sargent Irrigation ..... by (signature) 

**INSTRUCTIONS:** Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at <http://www.kdheks.gov/waterwell/index.html>

# **Sargent Irrigation**

WELL AND PUMP SERVICE

PO Box 268  
Holdrege, NE 68949

825 Brewster Road

Phone: (308) 995-6143  
1-800-860-2946

## **TEST HOLE LOG**

CUSTOMER: Brad Cox	
WELL ID:	
LOCATION: SE ¼, 32-T1S-R20W, Phillips Co., KS	
LATITUDE: 39.9161000	
LONGITUDE: -99.5970440	
FOOTAGES: 400' N of South line & 1977' W of East line	
DATE: 9/24/09	DRILLED BY: Kyle Schoff

SWL: 25'  
PWL: 29'  
GPM: 22

<u>from feet</u>	<u>to feet</u>	
0	3	Top soil
3	20	Clay and blue mud
20	40	Clay and blue mud with traces of fine sand
40	50	Fine to medium sand
50	60	Blue mud with thin fine to medium sand streaks
60	79	Fine to medium sand and coarse to fine gravel with thin limestone streaks
79	80	Gray shale

### **Well Information:**

Well depth: 80'  
Plain casing: 60'  
Perf. Set: 20'

Bore hole: 10"  
Perf. casing: 20'  
Gravel: 20-80'

Casing size: 5"  
Slot size: .016"  
Grout: 0-20'