

1 LOCATION OF WATER WELL		Fraction	Section Number	Township Number	Range Number		
County: <u>McPherson</u>		<u>NW 1/4 SW 1/4 SW 1/4</u>	<u>11</u>	<u>T 20 S</u>	<u>R 1 NW</u>		
Distance and direction from nearest town or city? <u>4 mi South + 1 mi East of Canton, Ks.</u>			Street address of well if located within city?				
2 WATER WELL OWNER: <u>MILFRED SCHMIOT</u>							
RR#, St. Address, Box # <u>Rt. 1</u>			Board of Agriculture, Division of Water Resources				
City, State, ZIP Code <u>CANTON, Ks.</u>			Application Number: <u>33164</u>				
3 DEPTH OF COMPLETED WELL: <u>58</u> ft. Bore Hole Diameter: <u>30</u> in. to <u>58</u> ft., and in. to ft.							
Well Water to be used as:							
1 Domestic		3 Feedlot	5 Public water supply	8 Air conditioning	11 Injection well		
2 Irrigation		4 Industrial	6 Oil field water supply	9 Dewatering	12 Other (Specify below)		
			7 Lawn and garden only	10 Observation well			
Well's static water level <u>10</u> ft. below land surface measured on <u>7</u> month <u>25</u> day <u>80</u> year							
Pump Test Data							
Est. Yield <u>400</u> gpm:		Well water was <u>55</u> ft. after <u>2</u> hours pumping <u>425</u> gpm					
		Well water was ft. after hours pumping gpm					
4 TYPE OF BLANK CASING USED:							
1 Steel		3 RMP (SR)	5 Wrought iron	8 Concrete tile	Casing Joints: Glued Clamped <u>X</u>		
2 PVC		4 ABS	6 Asbestos-Cement	9 Other (specify below)	Welded		
			7 Fiberglass		Threaded		
Blank casing dia <u>16</u> in. to <u>38</u> ft., Dia in. to ft., Dia in. to ft.							
Casing height above land surface <u>24</u> in., weight <u>32</u> lbs./ft. Wall thickness or gauge No. <u>75 in</u>							
TYPE OF SCREEN OR PERFORATION MATERIAL:							
1 Steel		3 Stainless steel	5 Fiberglass	8 RMP (SR)	11 Other (specify)		
2 Brass		4 Galvanized steel	6 Concrete tile	9 ABS	12 None used (open hole)		
Screen or Perforation Openings Are:							
1 Continuous slot		3 Mill slot	5 Gauzed wrapped	8 Saw cut	11 None (open hole)		
2 Louvered shutter		4 Key punched	6 Wire wrapped	9 Drilled holes			
			7 Torch cut	10 Other (specify)			
Screen-Perforation Dia <u>16</u> in. to <u>58</u> ft., Dia in. to ft., Dia in. to ft.							
Screen-Perforated Intervals: From <u>38</u> ft. to <u>58</u> ft., From ft. to ft., From ft. to ft.							
Gravel Pack Intervals: From <u>15</u> ft. to <u>58</u> ft., From ft. to ft., From ft. to ft.							
5 GROUT MATERIAL:							
1 Neat cement		2 Cement grout	3 Bentonite	4 Other			
Grouted Intervals: From <u>3</u> ft. to <u>15</u> ft., From ft. to ft., From ft. to ft.							
What is the nearest source of possible contamination:							
1 Septic tank		4 Cess pool	7 Sewage lagoon	10 Fuel storage	14 Abandoned water well		
2 Sewer lines		5 Seepage pit	8 Feed yard	11 Fertilizer storage	15 Oil well/Gas well		
3 Lateral lines		6 Pit privy	9 Livestock pens	12 Insecticide storage	16 Other (specify below)		
				13 Watertight sewer lines			
Direction from well: <u>South</u> How many feet <u>500</u> ? Water Well Disinfected? Yes No <u>X</u>							
Was a chemical/bacteriological sample submitted to Department? Yes No <u>X</u> If yes, date sample was submitted month day year: Pump Installed? Yes <u>X</u> No							
If Yes: Pump Manufacturer's name <u>WESTERN LAND ROLLER</u> Model No. <u>6M</u> HP <u>40</u> Volts							
Depth of Pump Intake <u>55</u> ft. Pumps Capacity rated at <u>400 gpm</u> gal./min.							
Type of pump:							
1 Submersible		2 Turbine	3 Jet	4 Centrifugal	5 Reciprocating		
					6 Other		
6 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on <u>7</u> month <u>26</u> day <u>1980</u> year							
and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>138</u>							
This Water Well Record was completed on <u>8</u> month <u>26</u> day <u>80</u> year under the business name of <u>PETERSON IRR. INC.</u> by (signature) <u>Mike Peterson</u>							
7 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
		0	4	Top Soil			
		4	12	Brown Sandy Clay			
		12	16	Gray Sandy Clay			
		16	20	Fine Sand			
		20	27	Fine Sand with Brown Clay			
		27	34	Fine to Medium Sand			
		34	36	Brown Sandy Clay			
		36	40	Medium Sand + Gravel			
		40	41	Brown Clay			
		41	57	Medium Sand			
ELEVATION:		57	58	Green Shale			
Depth(s) Groundwater Encountered 1. <u>16</u> ft. 2. ft. 3. ft. 4. ft. (Use a second sheet if needed)							
INSTRUCTIONS: Use typewriter or ball point pen, please press firmly and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Water Well Contractors, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.							

OFFICE USE ONLY

T

30

R

1

EWD

SEC.

11

NW 1/4 SW 1/4 SW 1/4