

102 1/2 N. SANTA FE
PHONE 7-1532

WATER WELLS
TEST HOLES

SALINA, KANSAS
BOX 477

LOG OF WELL

✓ ~~★~~
Ritz Station
NAME Illips Pipe Line Company HOLE NO. 2 DATE DRILLED 6/19/51
LOCATION SW SW sec. 7 T. 20S., R. 1W, McPherson Co.
About 40' east of hole No. 1
TYPE OF WELL Industrial TOPOGRAPHY Upland
DEPTH 44 FEET. DIAM. OF HOLE 8 INCHES. DEPTH TO WATER _____ FEET
CASING DIAM. 6 INCHES. SET AT 44 FEET. FINISH 3" slotted open end
YIELD Bailed 15 gallons per minute with 5' drawdown.
REMARKS Grouted 13'

DESCRIPTION OF MATERIAL	THICKNESS (FEET)	DEPTH (FEET)	DRILLING CHARACTER & REMARKS
Silt, clay.	3	3	Drilling 8" hole
Sand, very fine mixed with silt.	3	6	(Little gravel, medium to fine.
Silt and clay, greenish-grey and buff to tan; contains some gravel, medium to fine sand, and caliche.	33	39	
Gravel, fine to medium and sand, contains much silt, buff.	5	44	
Shale, gray-green.		44 1/2	