

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
County: Rice	NW 1/4 SE 1/4 SW 1/4	11	T 20 S	R 10 E/W

Distance and direction from nearest town or city street address of well if located within city?  
 Approximately 3 miles north and 3/4 mile east of Raymond

2 WATER WELL OWNER:	Clyde Ricker	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	565 Ave. N	Application Number: 42,036
City, State, ZIP Code :	Raymond, KS 67573	

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL: 134 ft. ELEVATION: Unknown
	Depth(s) Groundwater Encountered 1. . . . . ft. 2. . . . . ft. 3. . . . . ft.
	WELL'S STATIC WATER LEVEL 14 ft. below land surface measured on mo/day/yr 5-17-96
	Pump test data: Well water was not ch'd ft. after . . . . . hours pumping . . . . . gpm
	Est. Yield unknown gpm: Well water was . . . . . ft. after . . . . . hours pumping . . . . . gpm
Bore Hole Diameter: 18 in. to 133 ft., and . . . . . in. to . . . . . ft.	
WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well	
1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)	
2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well . . . . .	
Was a chemical/bacteriological sample submitted to Department? Yes. . . . . No. . . . . X. . . . . If yes, mo/day/yr sample was submitted	
Water Well Disinfected? Yes . . . . . No X	

5 TYPE OF BLANK CASING USED:	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued . . X. . . Clamped . . . . .
1 Steel	3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below) Welded . . . . .
2 PVC	4 ABS	7 Fiberglass	Threaded . . . . .
Blank casing diameter . . . . . 10 in. to . . . . . 83 ft., Dia . . . . . in. to . . . . . ft., Dia . . . . . in. to . . . . . ft.	Casing height above land surface . . . . . 12 in., weight . . . . . 7.80 lbs./ft. Wall thickness or gauge No. . . . . 365		
TYPE OF SCREEN OR PERFORATION MATERIAL:		7 PVC	10 Asbestos-cement
1 Steel	3 Stainless steel	5 Fiberglass	8 RMP (SR)
2 Brass	4 Galvanized steel	6 Concrete tile	9 ABS
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped	8 Saw cut
1 Continuous slot	3 Mill slot	6 Wire wrapped	9 Drilled holes
2 Louvered shutter	4 Key punched	7 Torch cut	10 Other (specify) . . . . .
SCREEN-PERFORATED INTERVALS: From . . . . . 83 ft. to . . . . . 133 ft., From . . . . . ft. to . . . . . ft.		From . . . . . ft. to . . . . . ft., From . . . . . ft. to . . . . . ft.	
GRAVEL PACK INTERVALS: From . . . . . 20 ft. to . . . . . 133 ft., From . . . . . ft. to . . . . . ft.		From . . . . . ft. to . . . . . ft., From . . . . . ft. to . . . . . ft.	

6 GROUT MATERIAL:	1 Neat cement	2 Cement grout	3 Bentonite	4 Other . . . . . Bentonite Holeplug . . . . .
Grout Intervals: From . . . . . ft. to . . . . . ft., From . . . . . ft. to . . . . . ft., From . . . . . ft. to . . . . . ft.	From . . . . . 0 ft. to . . . . . 20 ft.			
What is the nearest source of possible contamination:		10 Livestock pens	14 Abandoned water well	
1 Septic tank	4 Lateral lines	7 Pit privy	11 Fuel storage	15 Oil well/Gas well
2 Sewer lines	5 Cess pool	8 Sewage lagoon	12 Fertilizer storage	16 Other (specify below)
3 Watertight sewer lines	6 Seepage pit	9 Feedyard	13 Insecticide storage	None known . . . . .
Direction from well?		How many feet?		

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	4	Topsoil			
4	9	Clay, brown			
9	22	SAnd, fine			
22	25	Clay, brown			
25	30	Clay, gray			
30	35	Sand, fine			
35	40	Clay, gray			
40	48	Sand, fine			
48	80	Clay, brown, gray			
80	100	Sandstone with clay, yellow			
100	133	Sandstone, clean, loose			
133		Shale, hard			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) <u>constructed</u> , (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) . . . . . 5-17-96 . . . . . and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. . . . . 185 . . . . . This Water Well Record was completed on (mo/day/yr) . . . . . 6-3-96 . . . . . under the business name of <u>Clarke Well &amp; Equipment, Inc.</u> . . . . . by (signature) <i>Clyde Ricker</i>
---