


USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment (Water well Contractors) Topeka, Kansas 66620

| | |
|--|--|
| 1. Location of well: County <u>Rice</u> Fraction <u>1/4 C 1/4 NW 1/4</u> Section number <u>10</u> Township number T <u>20</u> S R <u>10</u> (E/W) | |
| 2. Distance and direction from nearest town or city: <u>4-W 1 1/2 E side from Chase, Ks.</u> Street address of well location if in city: | |
| 3. Owner of well: <u>Leonard Ricker</u> R.R. or street: <u>none</u> City, state, zip code: <u>Raymond, Ks.</u> | |
| 4. Locate with "X" in section below: Sketch map:  | |
| 6. Bore hole dia. <u>10</u> in. Completion date <u>11-19-75</u> Well depth <u>100</u> ft. | |
| 7. <input checked="" type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary | |
| 8. Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other | |
| 9. Casing: Material <u>PVC</u> Height: Above or below Threaded <input type="checkbox"/> Welded <input type="checkbox"/> Surface <u>1 1/2</u> in. RMP <input type="checkbox"/> PVC <input checked="" type="checkbox"/> Weight _____ lbs./ft. Dia. <u>3 1/2</u> in. to <u>100</u> ft. depth Wall Thickness: inches or Dia. _____ in. to _____ ft. depth gage No. <u>258</u> | |
| 5. Type and color of material | From To |
| <u>Sandy top soil</u> | 0 2 |
| <u>Fine sand</u> | 2 14 |
| <u>clay</u> | 14 25 |
| <u>sandy clay</u> | 25 33 |
| <u>Clay</u> | 33 76 |
| <u>Fine sand & clay</u> | 76 100 |
| 10. Screen: Manufacturer's name <u>Castalined</u> Type <u>PVC</u> Dia. _____ Slot/gauge <u>1/16</u> Length <u>20</u> Set between <u>80</u> ft. and <u>100</u> ft. ft. and _____ ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material <u>1/2 3/4 3/8</u> | |
| 11. Static water level: _____ mo./day/yr. <u>18</u> ft. below land surface Date <u>11-19-75</u> | |
| 12. Pumping level below land surfaces: <u>45</u> ft. after <u>1</u> hrs. pumping <u>10</u> g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield <u>40</u> g.p.m. | |
| 13. Water sample submitted: _____ mo./day/yr. <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Date <u>11-19-75</u> | |
| 14. Well head completion: <input type="checkbox"/> Pitless adapter _____ Inches above grade | |
| 15. Well grouted? <input checked="" type="checkbox"/> With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <u>0</u> ft. to <u>10</u> ft. | |
| 16. Nearest source of possible contamination: ft. <u>3000</u> Direction <u>N.E.</u> Type <u>septic</u> Well disinfected upon completion? <u>HTH</u> Yes <input type="checkbox"/> No | |
| 17. Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of drop pipe _____ ft. capacity _____ g.p.m. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other | |
| (Use a second sheet if needed) | |
| 18. Elevation: | 19. Remarks: |
| Topography: <input type="checkbox"/> Hill <input checked="" type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley | 20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Rosemarie Bemis 134</u> Business name _____ License No. _____ Address <u>Great Bend, Ks. 67530</u> Signed <u>Sandy K. Vigne</u> Date <u>11-19-75</u> Authorized representative |

20 10 W 1 C 1/4 1/4 1/4 1/4