

1. Location of well: Barton		Fraction 1/4 NW 1/4 NE 1/4		Section number 3		Township number T 20 S R 11		Range number EW																																																										
2. Distance and direction from nearest town or city: 2 1/2 miles East of Ellinwood, KS Street address of well location if in city:					3. Owner of well: Larry Panning R.R. or street: (?) City, state, zip code: Ellinwood, KS 67526																																																													
4. Locate with "X" in section below: N Sketch map: N 1 Mile S E W					6. Bore hole dia. 24 in. Completion date 6-25-76 Well depth 48 ft.																																																													
5. Type and color of material <table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th style="width:80%;"></th> <th style="width:10%;">From</th> <th style="width:10%;">To</th> </tr> </thead> <tbody> <tr> <td>top soil</td> <td>0</td> <td>3</td> </tr> <tr> <td>brown & gray clay</td> <td>3</td> <td>17</td> </tr> <tr> <td>sand & gravel</td> <td>17</td> <td>33</td> </tr> <tr> <td>brown clay, sand stone streaks</td> <td>33</td> <td>37</td> </tr> <tr> <td>sand & gravel</td> <td>37</td> <td>45</td> </tr> <tr> <td>Dakota clay</td> <td>45</td> <td>48</td> </tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> </tbody> </table>						From	To	top soil	0	3	brown & gray clay	3	17	sand & gravel	17	33	brown clay, sand stone streaks	33	37	sand & gravel	37	45	Dakota clay	45	48																																					7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary				
						From	To																																																											
					top soil	0	3																																																											
					brown & gray clay	3	17																																																											
sand & gravel	17	33																																																																
brown clay, sand stone streaks	33	37																																																																
sand & gravel	37	45																																																																
Dakota clay	45	48																																																																
8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other					9. Casing: Material steel Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight 30.3 lbs./ft. Dia. 16 in. to 26 ft. depth Wall Thickness: inches or Dia. 16 in. to 48 ft. depth gage No. 7 ga.																																																													
10. Screen: Manufacturer's name Johnson Type 125 Irrigator Dia. 16" Slot/gauze 1/8" Length 20' Set between 26 ft. and 46 ft. Gravel pack? yes Size range of material 3/8-200					11. Static water level: _____ mo./day/yr. 16' ft. below land surface Date 2-31-76																																																													
12. Pumping level below land surfaces: N/C _____ ft. after _____ hrs. pumping _____ g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield _____ g.p.m.					13. Water sample submitted: _____ mo./day/yr. Yes ☐ No ☒ Date _____																																																													
14. Well head completion: Pitless adapter 12 inches above grade					15. Well grouted? yes With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.																																																													
16. Nearest source of possible contamination: ft. _____ Direction _____ Type _____ Well disinfected upon completion? ☒ Yes _____ No _____					17. Pump: Not installed ☐ Manufacturer's name EMC - Peerless Model number 12LB-1 HP 15 Volts --- Length of drop pipe 40' ft. capacity 900 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other																																																													
18. Elevation: 1771 Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley					19. Remarks: 24009 NOTE: There are two separate systems on this same quarter. 20 11 3 A SB																																																													
20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clayker Well & Eq., Inc. 185 Business name License No. _____ Address Great Bend, KS 67530 Signed _____ Date _____ Authorized representative					21. _____																																																													