

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

T R EW sec 1/4 1/4 1/4 No.

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

1 Location of well:	County Barton	Township name Comanche	Fraction C SW 1/4	Section number 19	Town number T 20 S	Range number R 11 W
---------------------	-------------------------	----------------------------------	-----------------------------	-----------------------------	------------------------------	-------------------------------

Distance and direction from nearest town or city:

4 mi. South of Ellinwood, KS

Street address of well location if in city:

3 Owner of well:

Kurt Rugan


Address:

Ellinwood, Kansas

Locate with "X" in section below:

N

Sketch map:



4 Well depth: **92** ft. Date of completion **2-17-75**
Well diameter **24** in.

5 ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug
☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary

6 Use: ☐ Domestic ☐ Public supply ☐ Industry
☒ Irrigation ☐ Air conditioning ☐ Commercial
☐ Test well ☐

7 Casing: Material **Steel** Height: above below
Threaded ☐ Welded ☒ Surface **12** in.
Diam. **16** in. to **40** ft. depth Drive shoe? ☐ Yes ☒ No
16 in. to **52** ft. depth

2 Type and color of material

From

To

Sandy top soil

0

5

Sandy clay

5

18

Sandy clay streaks

18

38

Sand & gravel

38

48

Brown clay & lime

48

52

Sand & gravel

52

72'

Yellow & gray clay & gravel streaks

72

78

Sand & gravel

78

92

8 Screen:

Manufacturer **Doerr**

Type **Double-slot** Dia. **16"**

Slot gauge **1/8** Length **48'**

Set between **40** ft. and **48** ft.

Fittings **52' & 92'**

Gravel pack ☒ Yes ☐ No Size range of material **3/8-200**

9 Static water level:

15 ft. below land surface Date **2-17-75**

10 Pumping level below land surfaces:

N/C

ft. after hrs. pumping g.p.m.

ft. after hrs. pumping g.p.m.

Estimated maximum yield g.p.m.

11 Water sample submitted:

☐ Yes ☒ No Date

12 Well head completion:

☐ Pitless adapter **12** inches above grade

13 Well grouted? ☒ Yes ☐ No

☒ Neat cement ☐ Bentonite

Depth: From **0** ft. to **10** ft.

14 Nearest source of possible contamination:

ft. Direction Type

Well disinfected upon completion? ☐ Yes ☒ No

15 Pump:

☒ Not installed

Manufacturer's name

Model number HP Volts

Length of drop pipe ft. capacity g.m.p.

Type:

☐ Submersible

☐ Turbine

☐ Jet

☐ Reciprocating

☐ Centrifugal

☐ Other

16 Remarks: elevation

Topography:

- ☐ Hill
☐ Slope
☐ Upland
☐ Valley

1800

17 Water well contractor's certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Clarke Well & Eq., Inc. **185**

Business name License No.

Address **Great Bend, KS**

Signed **[Signature]** Date **2-17-75**

Authorized representative