

1 LOCATION OF WATER WELL:		Fraction		Section Number		Township Number		Range Number		
County: Barton		SW ¼ SW ¼ NE ¼		20		T 20 S		R 11 NW		
Distance and direction from nearest town or city street address of well if located within city?										
Approx. 3½ miles south and 1/2 mile east of Ellinwood, KS										
2 WATER WELL OWNER: Barton Co. Land & Cattle										
RR#, St. Address, Box # : Route 2					Board of Agriculture, Division of Water Resources					
City, State, ZIP Code : Ellinwood, KS 67526					Application Number: not available					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:			4 DEPTH OF COMPLETED WELL: 88 ft. ELEVATION: unknown							
			Depth(s) Groundwater Encountered 1. 23 ft. 2. ft. 3. ft. WELL'S STATIC WATER LEVEL 23 ft. below land surface measured on mo/day/yr 8/22/86 Pump test data: Well water was not checked ft. after hours pumping gpm Est. Yield unknown gpm: Well water was ft. after hours pumping gpm Bore Hole Diameter 18 in. to 87 ft., and in. to ft. WELL WATER TO BE USED AS: 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well Was a chemical/bacteriological sample submitted to Department? Yes No ☒ ; If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes ☒ No ☒							
5 TYPE OF BLANK CASING USED:										
1 Steel			3 RMP (SR)		5 Wrought iron		8 Concrete tile		CASING JOINTS: Glued ☒ Clamped	
2 PVC			4 ABS		6 Asbestos-Cement		9 Other (specify below)		Welded	
					7 Fiberglass				Threaded	
Blank casing diameter 8 in. to 67 ft., Dia. in. to ft., Dia. in. to ft.										
Casing height above land surface 12 in., weight 5.465 lbs./ft. Wall thickness or gauge No. 332										
TYPE OF SCREEN OR PERFORATION MATERIAL:										
1 Steel			3 Stainless steel		5 Fiberglass		8 RMP (SR)		10 Asbestos-cement	
2 Brass			4 Galvanized steel		6 Concrete tile		9 ABS		11 Other (specify)	
									12 None used (open hole)	
SCREEN OR PERFORATION OPENINGS ARE:										
1 Continuous slot			3 Mill slot		5 Gauzed wrapped		8 Saw cut		11 None (open hole)	
2 Louvered shutter			4 Key punched		6 Wire wrapped		9 Drilled holes			
					7 Torch cut		10 Other (specify)			
SCREEN-PERFORATED INTERVALS: From 67 ft. to 87 ft., From ft. to ft.										
GRAVEL PACK INTERVALS: From 62 ft. to 87 ft., From ft. to ft.										
Annular Fill From 10 ft. to 50 ft., From ft. to ft.										
6 GROUT MATERIAL:										
1 Neat cement			2 Cement grout		3 Bentonite		4 Other			
Grout Intervals: From 0 ft. to 10 ft., From 50 ft. to 62 ft., From ft. to ft.										
What is the nearest source of possible contamination:										
1 Septic tank			4 Lateral lines		7 Pit privy		10 Livestock pens		14 Abandoned water well	
2 Sewer lines			5 Cess pool		8 Sewage lagoon		11 Fuel storage		15 Oil well/Gas well	
3 Watertight sewer lines			6 Seepage pit		9 Feedyard		12 Fertilizer storage		16 Other (specify below)	
Direction from well? north How many feet? 500										
LITHOLOGIC LOG										
FROM	TO	LITHOLOGIC LOG		FROM	TO	LITHOLOGIC LOG				
0	23	Topsoil & sandy brown clay								
23	28	Sand & gravel, fine to medium								
28	31	Clay, white								
31	51	Sand & gravel, fine to very fine to medium								
51	54	Sandy brown clay								
54	56	Sand & gravel, fine to medium								
56	66	Tan clay w/streaks of sand @ 61'								
66	87	Sand & gravel, fine to very fine, some medium								
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 5/22/87 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 185 This Water Well Record was completed on (mo/day/yr) 5/22/87 under the business name of Clarke Well & Equipment, Inc. by (signature) <i>Clarke Well & Equipment, Inc.</i>										
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Office of Oil Field and Environmental Geology, Regulation and Permitting Section, Topeka, Kansas 66620-7500, Telephone: 913-862-9360. Send one to WATER WELL OWNER and retain one for your records.										