

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well: County <u>Barton</u>		Fraction <u>1/4 1/4 1/4</u>		Section number <u>27</u>	Township number T <u>20</u> S R <u>11</u> E/W
2. Distance and direction from nearest town or city: <u>45 3 3/4 E 1/4 S of Ellinwood.</u>				3. Owner of well: <u>Ken Peters</u> R.R. or street: City, state, zip code: <u>Ellinwood, Mo.</u>	
4. Locate with "X" in section below: N 1 Mile W E S 1 Mile		Sketch map: 		6. Bore hole dia. <u>29</u> in. Completion date <u>5-10-76</u> Well depth <u>82</u> ft.	
5. Type and color of material		From	To	7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary	
<u>Sandy Top Soil</u>		<u>0</u>	<u>2</u>	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other	
<u>Brown Clay</u>		<u>2</u>	<u>4</u>	9. Casing: Material <u>steel</u> Height <u>Above or below</u> Threaded ☐ Welded ☒ Surface <u>18</u> in. RMP ☐ PVC ☐ Weight <u> </u> lbs./ft. Dia. <u>16</u> in. to <u>82</u> ft. depth Wall Thickness: inches or Dia. <u> </u> in. to <u> </u> ft. depth gage No. <u>7</u>	
<u>Gray Clay</u>		<u>4</u>	<u>10</u>	10. Screen: Manufacturer's name <u>Doerr</u> Type <u>steel</u> Dia. <u>16</u> Slot/gauge <u>3/16</u> Length <u>36</u> Set between <u>46</u> ft. and <u>82</u> ft. ft. and <u> </u> ft. Gravel pack? ☒ Size range of material <u>1/2 3/4 1 1/2</u>	
<u>Brown Clay</u>		<u>10</u>	<u>15</u>	11. Static water level: <u>6</u> ft. below land surface Date <u>3-12-75</u> mo./day/yr.	
<u>Fine Yellow Brown Sand</u>		<u>15</u>	<u>24</u>	12. Pumping level below land surfaces: <u>14</u> ft. after <u>1</u> hrs. pumping <u>1200</u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u>1400</u> g.p.m.	
<u>Brown & Gray Clay</u>		<u>24</u>	<u>27</u>	13. Water sample submitted: <u>Yes</u> No Date <u>3-19-75</u> mo./day/yr.	
<u>Sand & Gravel Clear</u>		<u>27</u>	<u>42</u>	14. Well head completion: ☐ Pitless adapter <u> </u> inches above grade	
<u>loose. Medium</u>				15. Well grouted? ☒ With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.	
<u>Brown Clay</u>		<u>42</u>	<u>46</u>	16. Nearest source of possible contamination: ft. <u>14</u> Direction <u>n</u> Type <u>Drill</u> Well disinfected upon completion? ☐ Yes ☐ No	
<u>Sand & Gravel Clear Coarse loose</u>		<u>46</u>	<u>51</u>	17. Pump: ☐ Not installed Manufacturer's name <u>WLR</u> Model number <u>3-CHC-B</u> HP <u>40</u> Volts <u> </u> Length of drop pipe <u>65</u> ft. capacity <u>1200</u> g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
<u>Dark & Light Gray Clay</u>		<u>51</u>	<u>57</u>	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Rosenkrantz-Barnes</u> License No. <u>134</u> Business name <u> </u> Address <u>West Bend, Mo.</u> Signed <u>India Nelson</u> Date <u>9/30/76</u> Authorized representative	
<u>Sand & Gravel Clear Coarse loose</u>		<u>57</u>	<u>85</u>		
<u>some dark gravel in it.</u>					
<u>Shale</u>		<u>110</u>			
(Use a second sheet if needed)					
18. Elevation: <u>1760</u> Topography: ☐ Hill ☒ Slope ☐ Upland ☐ Valley		19. Remarks: <u>27763</u> <u>20 11 27 NAX</u>			

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5