

USE TYPEWRITER OR BALL
POINT PEN—PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82g-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

County		Fraction	Section number	Township number	Range number
Barton		1/4 1/4 CSE 1/4	29	T 20 S	R 11 E
1. Location of well: Distance and direction from nearest town or city: 4 3/4 miles South and 3/4 mile east of Ellinwood, KS Street address of well location if in city:			3. Owner of well: Marvin Sessler R.R. or street: Route 2 City, state, zip code: Ellinwood, KS 67526		
4. Locate with "X" in section below: N W E S 1 Mile		Sketch map: 1 Mile		6. Bore hole dia. 24 in. Completion date 4-8-76 Well depth 100 ft.	
5. Type and color of material		From	To	7. Cable tool Rotary Driven Dug Hollow rod Jetted Bored X Reverse rotary	
Top soil		0	3	8. Use: Domestic Public supply Industry X Irrigation Air conditioning Stock Lawn Oil field water Other	
Brown & gray clay & lime streaks		3	31	9. Casing: Material Steel Height: Above or below Threaded Welded X Surface 12 in. RMP PVC Weight 30.3 lbs./ft. Dia. 16 in. to 60 ft. depth Wall Thickness: inches or Dia. in. to ft. depth gage No. 7 ga.	
Brown clay & gravel		31	35	10. Screen: Manufacturer's name W. A. Brown Type Double-slot Dia. 16" Slot gauge 1/8 Length 40' Set between 60 ft. and 100 ft. Gravel pack? Yes Size range of material 3/8-200	
Sand & gravel		35	48	11. Static water level: mo./day/yr. 16 ft. below land surface Date 2-30-76	
Brown clay & lime streaks		48	62	12. Pumping level below land surfaces: N/C ft. after hrs. pumping g.p.m. ft. after hrs. pumping g.p.m. Estimated maximum yield g.p.m.	
Brown clay & gravel streaks		62	68	13. Water sample submitted: mo./day/yr. Yes X No Date	
Sand & gravel		68	100	14. Well head completion: Pitless adapter 12 Inches above grade	
				15. Well grouted? Yes With: X Neat cement Bentonite Concrete Depth: From 0 ft. to 10 ft.	
				16. Nearest source of possible contamination: ft. Direction Type Well disinfected upon completion? Yes X No	
				17. Pump: Manufacturer's name FMC Corp./Peerless Model number 12MB-3 HP 50 Volts Length of drop pipe 60 ft. capacity 900 g.p.m. Type: Submersible X Turbine Jet Reciprocating Centrifugal Other	
18. Elevation: 1777'		19. Remarks: (Use a second sheet if needed)		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name License No. Address Great Bend, KS Signed Date 4-14-76	

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5