

WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.

1 LOCATION OF WATER WELL: County: Barton		Fraction 1/4 NW 1/4 NE 1/4 NW 1/4		Section Number 26		Township No. T 20 S		Range Number R 11 ☐ E ☒ W																																																																			
2 WATER WELL OWNER: Jolene Bryant RR#, Street Address, Box #: 1433 SE 50 Rd City, State, ZIP Code : Ellinwood, KS 67530				Global Positioning System (GPS) information: Latitude: 38.288786 (in decimal degrees) Longitude: -98.510463 (in decimal degrees) Elevation: unknown Datum: ☐ WGS 84, ☒ NAD 83, ☐ NAD 27 Collection Method: ☒ GPS unit (Make/Model: WAAS) ☐ Digital Map/Photo, ☐ Topographic Map, ☐ Land Survey Est. Accuracy: ☐ <3 m, ☒ 3-5 m, ☐ 5-15 m, ☐ >15 m																																																																							
				3 LOCATE WELL WITH AN "X" IN SECTION BOX: 																																																																							
4 DEPTH OF COMPLETED WELL 60 ft. Depth(s) Groundwater Encountered (1) 13.10 ft. (2) ft. (3) ft. WELL'S STATIC WATER LEVEL 13.10 ft. below land surface measured on mo/day/yr 9/9/11 Pump test data: Well water was Not checked ft. after hours pumping gpm EST. YIELD gpm. Well water was ft. after hours pumping gpm Bore Hole Diameter 9 in. to 60 ft., and in. to ft. WELL WATER TO BE USED AS: ☐ Public water supply ☐ Geothermal ☐ Injection well ☒ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☐ Other (Specify below) ☐ Irrigation ☐ Industrial ☐ Domestic-lawn & garden ☐ Monitoring well Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No If yes, mo/day/yr sample was submitted Water well disinfected? ☒ Yes ☐ No																																																																											
5 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other CASING JOINTS: ☒ Glued ☐ Clamped ☐ Welded ☐ Threaded Casing diameter in. to ft., Diameter 5 in. to 50 ft., Diameter in. to ft. Casing height above land surface 24 in., Weight 2.36 lbs./ft., Wall thickness or gauge No. 215 TYPE OF SCREEN OR PERFORATION MATERIAL: ☐ Steel ☐ Stainless Steel ☒ PVC ☐ Other (Specify) ☐ Brass ☐ Galvanized Steel ☐ None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: ☐ Continuous slot ☒ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole) ☐ Louvered shutter ☐ Key punched ☐ Wire wrapped ☐ Saw cut ☐ Other (specify) SCREEN-PERFORATED INTERVALS: From 50 ft. to 60 ft., From ft. to ft. GRAVEL PACK INTERVALS: From 24 ft. to 60 ft., From ft. to ft. 6 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☒ Other Compacted Soil Grout Intervals: From ft. to ft., From 5 ft. to 24 ft., From 0 ft. to 5 ft. What is the nearest source of possible contamination: ☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☐ Other (specify below) ☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☐ Fuel storage ☐ Abandoned water well ☐ Watertight sewer lines ☐ Seepage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well None Known Direction from well Distance from well 																																																																											
<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>FROM</th> <th>TO</th> <th>LITHOLOGIC LOG</th> <th>FROM</th> <th>TO</th> <th>LITHO. LOG (cont.) or PLUGGING INTERVALS</th> </tr> </thead> <tbody> <tr> <td>0</td> <td>5</td> <td>Topsoil</td> <td> </td> <td> </td> <td> </td> </tr> <tr> <td>5</td> <td>11</td> <td>Clay, dark brown, soft, sandy</td> <td> </td> <td> </td> <td> </td> </tr> <tr> <td>11</td> <td>60</td> <td>Sand, coarse to fine with gravel, medium to fine, loose, clean</td> <td> </td> <td> </td> <td> </td> </tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> </tbody> </table>										FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS	0	5	Topsoil				5	11	Clay, dark brown, soft, sandy				11	60	Sand, coarse to fine with gravel, medium to fine, loose, clean																																													
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS																																																																						
0	5	Topsoil																																																																									
5	11	Clay, dark brown, soft, sandy																																																																									
11	60	Sand, coarse to fine with gravel, medium to fine, loose, clean																																																																									
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) 9/9/11 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 185 This Water Well Record was completed on (mo/day/year) 9/12/11 under the business name of Clarke Well & Equipment, Inc. by (signature) <i>[Signature]</i>																																																																											
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at http://www.kdheks.gov/waterwell/index.html .																																																																											