


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Barton	Fraction 1/4 1/4 SW 1/4	Section number 13	Township number T 20 S	Range number R 12 E
2. Distance and direction from nearest town or city: 3 miles Southwest of Ellinwood Street address of well location if in city:				3. Owner of well: Herbert Marchand R.R. or street: Route 2 City, state, zip code: Ellinwood, KS 67526		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 24 in. Completion date 3-20-78 Well depth 60 ft. (Pump Set - 5-5-78)		
				7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
5. Type and color of material		From		To		8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other
Top soil		0		2		9. Casing: Material Steel Height Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight 30.3 lbs./ft. Dia. 16 in. to 20 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth Gauge No. 7 ga.
Brown clay & sand		2		12		10. Screen: Manufacturer's name W. A. Brown Type Double-slot Dia. 16" Slot/gauze 1/8" Length 40 Set between 20 ft. and 60 ft. ft. and ☐ ft. Gravel pack? yes Size range of material 3/8-200
Sand & gravel		12		60		11. Static water level: ☐ mo./day/yr. N/C ft. below land surface Date ☐
						12. Pumping level below land surfaces: N/C ft. after ☐ hrs. pumping ☐ g.p.m. ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield ☐ g.p.m.
						13. Water sample submitted: ☐ mo./day/yr. ☒ Yes ☐ No Date 1-11-78
						14. Well head completion: ☐ Pitless adapter 12 Inches above grade
						15. Well grouted? yes With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.
						16. Nearest source of possible contamination: FIELD ft. ☐ Direction ☐ Type ☐ Well disinfected upon completion? ☐ Yes ☒ No
						17. Pump: ☐ Not installed Manufacturer's name Peerless Pump Model number 12MB-4 HP 80 Volts ☐ Length of drop pipe 50 ft. capacity 800 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other
						(Use a second sheet if needed)
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name Address Great Bend, KS 67530 License No. Signed [Signature] Date 5-10-78 Authorized representative		
Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5