


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

County	Barton	Fraction	C 1/4 NW 1/4 SE 1/4	Section number	20	Township number	T 20 S R 12
1. Location of well:		2. Distance and direction from nearest town or city: 5 miles south 1/2 west 1/4 north of <i>Dartmouth, Kansas</i>		3. Owner of well: <i>Specialty Feeders Inc.</i> R.R. or street: <i>Rt. 2</i> City, state, zip code: <i>Hoisington, Kansas 67544</i>			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <u>11</u> in. Completion date _____ Well depth <u>125</u> ft. <u>9-4-79</u>			
				7. Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary			
5. Type and color of material		From To		8. Use: Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☒ Stock ☐ Lawn ☐ Oil field water ☐ Other ☐			
top soil sandy		0 2		9. Casing: Material <u>PVC</u> Height: Above or below _____ Threaded _____ Welded _____ Surface <u>12</u> in. RMP _____ PVC ☒ Weight _____ lbs./ft. Dia. <u>6 1/2</u> in. to <u>125</u> ft. depth Wall Thickness: inches or _____ Dia. _____ in. to _____ ft. depth Gage No. <u>.280</u>			
clay and fine sand		2 27		☒ Screen: Manufacturer's name _____ <u>certain teed</u>			
sand and gravel		27 63		Type <u>PVC</u> Dia. <u>6 5/8</u> Slot/groove <u>1/16</u> Length <u>X 40 FT.</u> Set between <u>X 85</u> ft. and <u>N 125</u> ft. _____ ft. and _____ ft.			
clay		63 75		Gravel pack? ☒ Size range of material <u>3/4-3/8</u>			
sand and gravel		75 93		11. Static water level: _____ mo./day/yr., <u>29</u> ft. below land surface Date <u>8-10-79</u>			
clay		93 95		12. Pumping level below land surfaces: <u>NA</u> ____ ft. after ____ hrs. pumping ____ g.p.m. ____ ft. after ____ hrs. pumping ____ g.p.m.			
sand and gravel		95 125		Estimated maximum yield _____ g.p.m.			
				13. Water sample submitted: _____ mo./day/yr. ☒ Yes ☐ No Date <u>8-10-79</u>			
				14. Well head completion: ☒ Pitless adapter _____ <u>12</u> inches above grade			
				15. Well grouted? ☒ With: ☒ Neat cement _____ Bentonite _____ Concrete _____ Depth: From _____ ft. to <u>15</u> ft.			
				16. Nearest source of possible contamination: ft. <u>50</u> Direction <u>south</u> type <u>pits</u> Well disinfected upon completion? ☒ Yes ☐ No			
				17. Pump: ☒ Not installed Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of drop pipe _____ ft. capacity _____ g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other			
(Use a second sheet if needed)							
18. Elevation:	19. Remarks:			20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Rosencrantz-Bemis</u> <u>134</u> Business name License No. Address <u>Box 713 Great Bend, Ks</u> Signed <u>Fredrick Bader</u> Date <u>10/15/79</u> Authorized representative			
Topography: Hill _____ Slope _____ Upland _____ ☒ Valley							

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5