

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Barton	Fraction NE 1/4 NE 1/4 SE 1/4	Section number 20	Township number T 20 S	Range number R 12 E
2. Distance and direction from nearest town or city: 8 miles Southwest of Ellinwood, KS Street address of well location if in city:			3. Owner of well: Russell Grant R.R. or street: Route 2 City, state, zip code: Ellinwood, KS 67526			
4. Locate with "X" in section below: N W E S 1 Mile 1 Mile			Sketch map: Approx. 2000' North and 500' West of the SE Corner of Sec. 20			
5. Type and color of material			From	To	6. Bore hole dia. 9 in. Completion date 4-13-79 Well depth 61 ft. Pump Set 4-17-79	
Sandy top soil			0	7	7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary	
Brown clay			7	11	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other	
Gray clay			11	21	9. Casing: Material Styrene Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight 1.5 lbs./ft. Dia. 5 in. to 51 ft. depth Wall thickness: inches or Dia. ☐ in. to ☐ ft. depth Gauge No. 200	
Fine sand			21	24	10. Screen: Manufacturer's name Jess & Lowell Type Styrene 200 Dia. 5" Slot gauze 1/8" Length 10' Set between 51 ft. and 61 ft. Gravel pack? Yes Size range of material 3/8-200	
Sandy brown clay			24	43	11. Static water level: ☐ mo./day/yr. 22' 8" ft. below land surface Date 4-13-79	
Sand			43	47	12. Pumping level below land surface Not Checked ft. after ☐ hrs. pumping ☐ g.p.m. ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield ☐ g.p.m.	
Sand & gravel - Contains thin clay streaks			47	61	13. Water sample submitted: ☐ mo./day/yr. Yes ☒ No Date ☐	
					14. Well head completion: ☐ Pitless adapter 12 Inches above grade	
					15. Well grouted? Yes With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.	
					16. Nearest source of possible contamination: FIELD ft. ☐ Direction ☐ Type ☐ Well disinfected upon completion? ☒ Yes ☐ No	
					17. Pump: ☐ Not installed Manufacturer's name Berkeley Pump Co. Model number 4BL-12 HP 3/4 Volts 230 Length of drop pipe 42 ft. capacity 15 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
(Use a second sheet if needed)						
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name Great Bend, KS 67530 Address Great Bend, KS 67530 Signed [Signature] Date 4-18-79 Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5