

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Barton	Fraction NE 1/4 SW 1/4 NE 1/4	Section number 25	Township number T 20 S	Range number R 12 E
2. Distance and direction from nearest town or city: 4 1/2 miles Southwest of Ellinwood, KS Street address of well location if in city:				3. Owner of well: Vernon DeWerff R.R. or street: Route 2 City, state, zip code: Ellinwood, KS 67526		
4. Locate with "X" in section below: Sketch map: N W E S 1 Mile				6. Bore hole dia. 24 in. Completion date 12-7-76 Well depth 96 ft.		
5. Type and color of material				From	To	7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary
top soil				0	3	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other
brown clay & sand streaks				3	31	9. Casing: Material steel Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight 30.3 lbs./ft. Dia. 16 in. to 40 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 7 gao
sand & gravel & thin clay streak at 75'				31	96	10. Screen: Manufacturer's name Doerr Type double-slot Dia. 16" Slot/gauze 1/8" Length 56' Set between 40 ft. and 96 ft. Gravel pack? yes Size range of material 3/8-200
						11. Static water level: 14' 4" below land surface Date 11-26-76
						12. Pumping level below land surfaces: N/C ft. after hrs. pumping g.p.m. ft. after hrs. pumping g.p.m. Estimated maximum yield g.p.m.
						13. Water sample submitted: mo./day/yr. Yes ☒ No ☐ Date
						14. Well head completion: Pitless adapter 12 Inches above grade
						15. Well grouted? yes With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.
						16. Nearest source of possible contamination: ft. Direction Type Well disinfected upon completion? Yes ☒ No ☐
						17. Pump: Manufacturer's name Peerless Pump Model number 12MB-3 HP 50 Volts 460 Length of drop pipe 60 ft. capacity 900 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other
(Use a second sheet if needed)						
18. Elevation: Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Equip., Inc 185 Business name License No. Address Great Bend, KS 67530 Signed [Signature] Date 12-17-76 Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5