


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Barton	Fraction 1/4 1/4 CSE 1/4	Section number 25	Township number T 20 S	Range number R 12 E
2. Distance and direction from nearest town or city: 5 mi mi. South of Ellinwood, KS Street address of well location if in city:			3. Owner of well: Bill Madden R.R. or street: Rural Route City, state, zip code: Raymond, KS 67573		
4. Locate with "X" in section below: Sketch map: 			6. Bore hole dia. 24 in. Completion date 4-13-76 Well depth 100 ft.		
5. Type and color of material			7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
			8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
			9. Casing: Material Steel Height: ☐ Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight 30.3 lbs./ft. Dia. 16 in. to 40 ft. depth Wall thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 7 ga.		
			10. Screen: Manufacturer's name Doerr Type Double-slot Dia. 16" Slot/gauze 1/8 Length 60' Set between 40 ft. and 100 ft. Gravel pack? Yes Size range of material 3/8-200		
Top soil			From	To	11. Static water level: 13 1/2 ft. below land surface Date 2-29-76
XXXXXX Brown & gray clay			4	34	12. Pumping level below land surfaces: N/C ____ ft. after ____ hrs. pumping ____ g.p.m. ____ ft. after ____ hrs. pumping ____ g.p.m. Estimated maximum yield ____ g.p.m.
Sand & gravel			34	54	13. Water sample submitted: Yes ☒ No ☐ Date ____
Brown & gray clay			54	58	14. Well head completion: ☐ Pitless adapter 12 inches above grade
Sand & gravel			58	70	15. Well grouted? Yes With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.
Brown clay			70	75	16. Nearest source of possible contamination: ft. ____ Direction ____ Type ____ Well disinfected upon completion? ____ Yes ☒ No ☐
Sand, gravel & thin clay streaks			75	85	17. Pump: Manufacturer's name EMC Corp./Peerless Not installed Model number 12MB-3 HP 40 Volts 460 Length of drop pipe XX60 ft. capacity 900 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other
Sand & gravel			85	100	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq, Inc. 185 Business name License No. Address Great Bend, KS Signed C. W. Clarke Date 4-14-76 Authorized representative
(Use a second sheet if needed)					
18. Elevation: Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley	19. Remarks: 				

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5