


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County <u>Barton</u>	Fraction <u>C 1/4 NE 1/4 NE 1/4</u>	Section number <u>28</u>	Township number <u>T 20 S R 12 E/W</u>	Range number
2. Distance and direction from nearest town or city: <u>5 mi S 6 mi E. 1/8 mi S - West side of rd. from Great Bend</u>		3. Owner of well: <u>Tom Edwards</u> R.R. or street: <u>RFD #3</u> City, state, zip code: <u>Great Bend, Ks. 67530</u>				
4. Locate with "X" in section below: 		Sketch map: <u>25.</u>		6. Bore hole dia. <u>11</u> in. Completion date <u>11-15-77</u> Well depth <u>80</u> ft.		
5. Type and color of material		From	To	7. ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
<u>Sandy top soil</u>		<u>0</u>	<u>2</u>	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
<u>Sandy brown clay</u>		<u>2</u>	<u>28</u>	9. Casing: Material <u>PVC</u> Height: Above or below Threaded ☐ Welded ☐ Surface <u>24</u> in. RMP ☐ PVC ☒ Weight ☐ lbs./ft.		
<u>Sand & gravel</u>		<u>28</u>	<u>46</u>	Dia. <u>4</u> in. to <u>80</u> ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. <u>237</u>		
<u>Brown & white clay</u>		<u>46</u>	<u>58</u>	10. Screen: Manufacturer's name <u>Certain</u> Type <u>PVC</u> Dia. <u>4</u> Slot <u>1/16</u> Length <u>25</u> Set between <u>55</u> ft. and <u>80</u> ft. Gravel pack? ☒ Size range of material <u>1/2 3/4 1 1/2</u>		
<u>Blue clay & blue gravel</u>		<u>58</u>	<u>80</u>	11. Static water level: <u>18</u> ft. below land surface Date <u>11-15-77</u> mo./day/yr.		
				12. Pumping level below land surfaces: <u>NA</u> ft. after ☐ hrs. pumping ☐ g.p.m. ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield ☐ g.p.m.		
				13. Water sample submitted: <u>Yes</u> ☒ No ☐ Date <u>11-16-77</u> mo./day/yr.		
				14. Well head completion: ☐ Pitless adapter ☐ Inches above grade		
				15. Well grouted? ☒ With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.		
				16. Nearest source of possible contamination: <u>20</u> ft. Direction <u>SE</u> Type <u>Septic</u> Well disinfected upon completion? <u>NA</u> Yes ☐ No ☐		
				17. Pump: <u>Not installed</u> Manufacturer's name <u>Beck</u> Model number <u>5CC</u> HP <u>1/2</u> Volts <u>230</u> Length of drop pipe <u>42</u> ft. capacity <u>10</u> g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
		(Use a second sheet if needed)				
18. Elevation:		19. Remarks:				
Topography: ☐ Hill ☐ Slope ☐ Upland ☒ Valley						
		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Rosemcrantz Bernis</u> <u>134</u> Business name License No. Address <u>Great Bend, Ks. 67530</u> Signed <u>Sandy Kilgus</u> Date <u>12-17-77</u> Authorized representative				

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5