


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County 05 Barton	Fraction ne 1/4 ne 1/4 se 1/4	Section number 35	Township number T 20 S R 12 E/W	Range number
2. Distance and direction from nearest town or city: 6-S 1-W 1/2-N of Ellinwood, Ks. Street address of Well location if in city:				3. Owner of well: Ron Rugan R.R. or street: none City, state, zip code: Ellinwood, Kansas 67526		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 29 in. Completion date _____ Well depth 134 ft. 5-29-75		
				7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
5. Type and color of material		From	To	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
sandy top soil		0	6	9. Casing: Material steel Height: Above or below _____ Threaded _____ Welded _____ Surface 18 in. RMP _____ PVC _____ Weight _____ lbs./ft. Dia. 16 in. to 134 ft. depth Wall Thickness: inches or Dia. _____ in. to _____ ft. depth gage No. 7		
brown clay		6	13	10. Screen: Manufacturer's name _____ Doerrs Type steel Dia. _____ Slot xxxx 3/16 Length 52 Set between 82 ft. and 134 ft. _____ ft. and _____ ft. Gravel pack? ☒ Size range of material 3/4 3/8		
fine sand & sandy brown clay		13	20	11. Static water level: _____ mo./day/yr. 28 ft. below land surface Date 12-20-74		
brown clay		20	50	12. Pumping level below land surfaces: 48 ft. after 1 hrs. pumping 800 g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield 1400+ g.p.m.		
brown & white clay		50	59	13. Water sample submitted: _____ mo./day/yr. ☒ Yes ☐ No Date 12-20-74		
sand & gravel w/lot of clay		59	66	14. Well head completion: ☐ Pitless adapter _____ Inches above grade		
sand & gravel w/some clay		66	77	15. Well grouted? ☒ With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.		
yellow brown clay		77	80	16. Nearest source of possible contamination: ft. 1/8 mi Direction south Type oilwell Well disinfected upon completion? ☒ Yes ☐ No		
sand & gravel med. loose w/little clay		80	96 1/2	17. Pump: _____ Not installed Manufacturer's name W.L.R. Model number 4-12BHC HP 60 Volts 460 Length of drop pipe 70 ft. capacity 1000 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
brown & clay		96 1/2	98			
sand & gravel clean med. loose		98	121			
blue gray clay		121	123			
sand & gravel loose med. dark colored		123	135			
blue gray clay & little sand		135	140			
hard rock		140				
(Use a second sheet if needed)						
18. Elevation: 1826 Topography: ☐ Hill ☐ Slope ☒ Upland ☐ Valley		19. Remarks: 23927 (CDD)		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Rosencrantz-Bemis 134 Business name License No. Address Great Bend, Kansas 67530 Signed S. Kulgoor Date 6-19-75 Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5