


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Barton	Fraction 1/4 C NE 1/4	Section number 36	Township number T 20	Range number S R 12 E/W
2. Distance and direction from nearest town or city: 8 S.			3. Owner of well: NORMAN KLEPPER			
Street address of well location if in city: Ellis Wood, KS			R.R. or street: R2 Ellis Wood, KS			
City, state, zip code:						
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 30 in. Completion date 11-19-76		
				Well depth 90 ft.		
				7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
5. Type and color of material		From		To		8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other
Top Soil - Clay		0		36		9. Casing: Material Steel Height: Above or below
Sand - Gravel		36		62		Threaded ☐ Welded ☒ Surface 24 in.
Clay		62		72		RMP ☐ PVC ☐ Weight 30 lbs./ft.
Sand - Gravel		72		90		Dia. 16 in. to 50 ft. depth Wall Thickness: inches or
						Dia. ☐ in. to ☐ ft. depth gage No. 3/16
						10. Screen: Manufacturer's name DOOR
						Type Steel Dia. 16"
						Slot/gauze 1/8" Length 40'
						Set between 50 ft. and 90 ft.
						Gravel pack? ☒ Size range of material 1/8 - 3/16"
						11. Static water level: 16 ft. below land surface Date 11-19-76
						12. Pumping level below land surfaces:
						49 ft. after 4 hrs. pumping 900 g.p.m.
						900 ft. after 4 hrs. pumping 900 g.p.m.
						Estimated maximum yield 1200 g.p.m.
						13. Water sample submitted: X Yes ☐ No Date 9-17-76
						14. Well head completion:
						☐ Pitless adapter 24 Inches above grade
						15. Well grouted? ☒ X
						With: ☒ Neat cement ☐ Bentonite ☐ Concrete
						Depth: From 0 ft. to 10 ft.
						16. Nearest source of possible contamination: live
						ft. 1300 Direction NE Type Stock
						Well disinfected upon completion? ☐ Yes ☒ No
						17. Pump: Not installed
						Manufacturer's name Goulds
						Model number 3125 HP 50 Volts 460
						Length of drop pipe 80 ft. capacity 900 g.p.m.
						Type:
						☐ Submersible ☒ Turbine
						☐ Jet ☐ Reciprocating
						☐ Centrifugal ☐ Other
18. Elevation:		19. Remarks:		20. Water well contractor's certification:		
Topography:				This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.		
☐ Hill				186		
☐ Slope				Kelly's Water Well Ser. Inc		
☒ Upland				Business name R2 Great Bend, KS		
☐ Valley				Address Kelly Price		
				Signed Kelly Price Date 12-30-76		
				Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5