

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County BARTON	Fraction SE 1/4 NW 1/4 SW 1/4	Section number 4	Township number T 20 S	Range number R 13 E															
2. Distance and direction from nearest town or city: 15 1/4 W.			3. Owner of well: Jerry Vernon																		
Street address of well location if in city: Great Bend, KS			City, state, zip code: R2, Great Bend, KS																		
4. Locate with "X" in section below:		Sketch map:			6. Bore hole dia. 7 in. Completion date 11-1-75 Well depth 50 ft.																
					7. ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary																
					8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other																
5. Type and color of material		<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th></th> <th>From</th> <th>To</th> </tr> </thead> <tbody> <tr> <td>Top soil - clay</td> <td>0</td> <td>16</td> </tr> <tr> <td>Sand - Gravel</td> <td>16</td> <td>29</td> </tr> <tr> <td>Clay</td> <td>29</td> <td>32</td> </tr> <tr> <td>Sand - Gravel</td> <td>32</td> <td>50</td> </tr> </tbody> </table>				From	To	Top soil - clay	0	16	Sand - Gravel	16	29	Clay	29	32	Sand - Gravel	32	50	9. Casing: Material ☐ Height: Above or below Threaded ☐ Welded ☐ Surface 12 in. RMP ☐ PVC ☒ Weight ☐ lbs./ft. Dia. 4 in. to 50 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. ☐	
						From	To														
Top soil - clay	0	16																			
Sand - Gravel	16	29																			
Clay	29	32																			
Sand - Gravel	32	50																			
10. Screen: Manufacturer's name MIPI Type PVC Dia. 4" Slot/gauze 1/8" Length 15' Set between 35 ft. and 50 ft. ☐ ft. and ☐ ft. Gravel pack? ☒ Size range of material 1/2" - 3/4"																					
					11. Static water level: ☐ mo./day/yr. 15 ft. below land surface Date 11-1-75																
					12. Pumping level below land surfaces: ☐ ft. after ☐ hrs. pumping ☐ g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield 40 g.p.m.																
					13. Water sample submitted: ☐ mo./day/yr. ☐ Yes ☒ No Date ☐																
					14. Well head completion: ☐ Pitless adapter 13 Inches above grade																
					15. Well grouted? ☒ With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 4 ft. to 14 ft.																
					16. Nearest source of possible contamination: ft. 60 Direction E Type SEPTIC TANKS Well disinfected upon completion? ☒ Yes ☐ No																
					17. Pump: ☒ Not installed Manufacturer's name ☐ Model number ☐ HP ☐ Volts ☐ Length of drop pipe ☐ ft. capacity ☐ g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other																
					20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Kellys Water Well Ser 184 Business name R2 Great Bend, KS License No. ☐ Address Kellys Signed Kelly Price Date 11-6 Authorized representative																
18. Elevation:		19. Remarks:																			
Topography: ☐ Hill ☐ Slope ☐ Upland ☒ Valley																					

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5