

1 LOCATION OF WATER WELL:		Fraction	Township Number	Range Number	
County: Barton	SW ¼ SW ¼ SW ¼	Section Number 10	T 20 S	R 13 W	
Distance and direction from nearest town or city street address of well if located within city? <u>Approx. 2 miles south of Great Bend, KS</u>					
2 WATER WELL OWNER:	Al Smith				
RR#, St. Address, Box # :	Route 2				
City, State, ZIP Code :	Great Bend, KS 67530				
			Board of Agriculture, Division of Water Resources		
			Application Number: <u>not required</u>		
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL: 65 ft. ELEVATION: unknown				
A diagram showing a section box divided into four quadrants labeled NW, NE, SE, and SW. An 'X' is marked in the SW quadrant. A north arrow points upwards next to the label 'N'. The vertical axis is labeled 'W' at the top and 'E' at the bottom.	Depth(s) Groundwater Encountered 1... 16 ft. 2... ft. 3... ft.				
	WELL'S STATIC WATER LEVEL ... 16 ft. below land surface measured on mo/day/yr ... 7-20-84				
	Pump test data: Well water was not ck'd ft. after hours pumping gpm				
	Est. Yield unknown gpm: Well water was ft. after hours pumping gpm				
	Bore Hole Diameter... 9 in. to 65 ft., and in. to ft.				
	WELL WATER TO BE USED AS: 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well				
Was a chemical/bacteriological sample submitted to Department? Yes.....No..X.....; If yes, mo/day/yr sample was submitted					
Water Well Disinfected? Yes X No					
5 TYPE OF BLANK CASING USED:					
Blank casing diameter . . . 5 in. to 25 ft., Dia. . . in. to . . . ft., Dia. . . in. to . . . ft.					
Casing height above land surface . . . 24 in., weight . . . 2.277 lbs./ft. Wall thickness or gauge No. . . 214					
TYPE OF SCREEN OR PERFORATION MATERIAL:					
SCREEN OR PERFORATION OPENINGS ARE:					
SCREEN-PERFORATED INTERVALS: From . . . 25 ft. to 65 ft., From . . . ft. to . . . ft.					
GRAVEL PACK INTERVALS: From . . . 18 ft. to 65 ft., From . . . ft. to . . . ft.					
Annular Fill From 10 ft. to 14 ft., From . . . ft. to . . . ft.					
6 GROUT MATERIAL:					
Grout Intervals: From . . . 0 ft. to 10 ft., From . . . 14 ft. to . . . 18 ft., From . . . ft. to . . . ft.					
What is the nearest source of possible contamination:					
Direction from well? southeast How many feet? 150					
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
0	21	Topsoil & soft brown clay			
21	50	Sand & gravel, fine to med.			
50	65	Sand & gravel med. to coarse			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 7-20-84 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 185 This Water Well Record was completed on (mo/day/yr) 8-8-84 under the business name of Clarke Well & Eq., Inc. by (signature)					
INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.					