


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County <u>Barton</u>	Fraction <u>NW 1/4 SW 1/4 SW 1/4</u>	Section number <u>10</u>	Township number <u>20</u> S <u>13</u> W	Range number <u>13</u> W
2. Distance and direction from nearest town or city: <u>2 1/2 mi. S of Great Bend</u> Street address of well location if in city:				3. Owner of well: <u>C & P Electric</u> R.R. or street: <u>Highway 281 South</u> City, state, zip code: <u>Great Bend, KS.</u>		
4. Locate with "X" in section below: Sketch map: 				6. Bore hole dia. <u>9 3/8</u> in. Completion date <u>8-25-76</u> Well depth <u>80</u> ft.		
				7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
				8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
				9. Casing: Material <u>PVC</u> Height: Above or below Threaded ☐ Welded ☐ Surface <u>18</u> in. RMP ☐ PVC ☐ Weight <u>165</u> lbs./ft. Dia. <u>5</u> in. to <u>80</u> ft. depth Wall Thickness: inches or Dia. <u>5</u> in. to <u>80</u> ft. depth gage No. <u>174</u>		
5. Type and color of material				From	To	10. Screen: Manufacturer's name <u>R P</u>
<u>Top Soil</u>				<u>0</u>	<u>5</u>	Type <u>PVC</u> Dia. <u>5</u>
<u>Fine Sand Brown Clay</u>				<u>5</u>	<u>16</u>	Slot/gauze <u>1/16</u> Length <u>20</u>
<u>Brown Clay</u>				<u>16</u>	<u>22</u>	Set between <u>60</u> ft. and <u>80</u> ft.
<u>Sand Gravel</u>				<u>22</u>	<u>80</u>	Gravel pack? ☐ Size range of material <u>3/4 - 3/8</u>
						11. Static water level: <u>16</u> ft. below land surface Date <u>8-25-76</u>
						12. Pumping level below land surfaces: <u>16</u> ft. after <u>1</u> hrs. pumping <u>50</u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u>50</u> g.p.m.
						13. Water sample submitted: ☒ Yes ☐ No Date <u>8-25-76</u>
						14. Well head completion: ☒ Pitless adapter <u>18</u> inches above grade
						15. Well grouted? ☒ With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From <u>16</u> ft. to <u>22</u> ft. <u>0-16</u> in.
						16. Nearest source of possible contamination: ft. <u>150</u> Direction <u>W</u> Type <u>Well</u> Well disinfected upon completion? ☒ Yes ☐ No
						17. Pump: ☒ Not installed Manufacturer's name <u> </u> Model number <u> </u> HP <u> </u> Volts <u> </u> Length of drop pipe <u> </u> ft. capacity <u> </u> g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other
(Use a second sheet if needed)						
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Benjamin - Ben</u> <u>134</u> Business name <u>Great Bend, KS</u> License No. <u> </u> Address <u> </u> Signed <u> </u> Date <u>8/27/76</u> Authorized representative		
Topography: ☐ Hill ☐ Slope ☒ Upland ☐ Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5