


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Barton	Fraction 1/4 c 1/4 se 1/4	Section number 20	Township number T 20 S	Range number R 13 E (W)
2. Distance and direction from nearest town or city: 5-S 1-W 1/4-N 1/4-W into field from Great Bend, Kansas				3. Owner of well: Harry Schartz R.R. or street: 1423 Baker City, state, zip code: Great Bend, Kansas 67530		
4. Locate with "X" in section below: N W E S 1 Mile Sketch map: 				6. Bore hole dia. 29 in. Completion date _____ Well depth 82 ft. 5-4-75		
5. Type and color of material				7. ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
				8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
				9. Casing: Material steel Height: Above or below _____ Threaded _____ Welded _____ Surface 18 in. RMP _____ PVC _____ Weight _____ lbs./ft. Dia. 16 in. to 82 ft. depth Wall Thickness: inches or _____ Dia. _____ in. to _____ ft. depth Gage No. 7		
				10. Screen: Manufacturer's name _____ Doerrs Type steel Dia. _____ Slot 3/16 Length 40 Set between 42 ft. and 82 ft. _____ ft. and _____ ft. Gravel pack? ☒ Size range of material 3/4 3/8		
				11. Static water level: _____ mo./day/yr. 13 ft. below land surface Date 1-20-72		
				12. Pumping level below land surfaces: 39 ft. after 1 hrs. pumping 800 g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield 1400 g.p.m.		
				13. Water sample submitted: _____ mo./day/yr. ☒ Yes ☐ No Date 1-20-72		
				14. Well head completion: ☐ Pitless adapter _____ Inches above grade		
				15. Well grouted? ☒ With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.		
				16. Nearest source of possible contamination: ft. 1 mi Direction east Type corrall Well disinfected upon completion? ☒ Yes ☐ No		
				17. Pump: _____ Not installed Manufacturer's name W.L.B. Model number 3-120M HP 40 Volts 460 Length of drop pipe 60 ft. capacity 1000 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
(Use a second sheet if needed)						
18. Elevation:		19. Remarks: 1750		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Rosencrantz-Bemis 134 Business name License No. Address Great Bend, Kansas 67530 Signed S. Kilgore Date 1-19-72 Authorized representative		
Topography: ☐ Hill ☐ Slope ☒ Upland ☐ Valley						