

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Barton	Fraction 1/4 1/4 NW 1/4	Section number 21	Township number 20 T 20 S R 13 E/W	Range number
2. Distance and direction from nearest town or city: 35.1 W		3. Owner of well: Date Engleman		R2 Great Bend, KS		
Street address of well location if in city: Great Bend, KS		City, state, zip code:				
4. Locate with "X" in section below: N W E S 1 Mile 1 Mile		Sketch map: 		6. Bore hole dia. 30 in. Completion date 12-7-76 Well depth 83 ft.		
5. Type and color of material		From	To	7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
Top Soil - Clay		0	30	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
Sand - Gravel - Clay		30	50	9. Casing: Material ☐ Height: Above or below Threaded ☐ Welded ☐ Surface 24 in. RMP ☐ PVC ☒ Weight ☐ lbs./ft. Dia. 4 1/2 in. to 53 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 50		
Sand - Gravel		50	83	10. Screen: Manufacturer's name Peckless Type PVC Dia. 1 1/2 " Slot/gauze 1/8 " Length 30 " Set between 53 ft. and 83 ft. ft. and ft. Gravel pack? ☒ Size range of material 1/8"-3/4"		
Clay		83	88	11. Static water level: ☐ mo./day/yr. 13 1/2 ft. below land surface Date 12-7-76		
				12. Pumping level below land surfaces: ft. after hrs. pumping g.p.m. 42 ft. after 4 hrs. pumping 1000 g.p.m. Estimated maximum yield 1300 g.p.m.		
				13. Water sample submitted: ☐ mo./day/yr. ☒ Yes ☐ No Date 11-7-76		
				14. Well head completion: ☐ Pitless adapter 24 inches above grade		
				15. Well grouted? ☒ With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 20 ft.		
				16. Nearest source of possible contamination: LIVE ft. 1500 Direction SW Type STOCK Well disinfected upon completion? ☐ Yes ☒ No		
				17. Pump: ☐ Not installed Manufacturer's name Grundfos Model number 3125 HP 50 Volts 460 Length of drop pipe 70 ft. capacity 1000 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
18. Elevation: 1078		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Kelly's Water Well Serv Business name R2 Great Bend, KS License No. 186 Address R2 Great Bend, KS Signed Kelly Price Date 2-15-77 Authorized representative		