


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Barton	Fraction 1/4 1/4 CNE 1/4	Section number 24	Township number T 20 S	Range number R 13 E
2. Distance and direction from nearest town or city: 6 1/2 miles Southeast of Great Bend, KS Street address of well location if in city:				3. Owner of well: Marvin Johnston, Jr. R.R. or street: 2015 Forest City, state, zip code: Great Bend, KS 67530		
4. Locate with "X" in section below: N  S 1 Mile				Sketch map:		
5. Type and color of material				From	To	
Top soil				0	2	
Gray clay				2	16	
Sand & sandy clay				16	23	
Sand & gravel & thin clay streak at 35 & 37				23	62	
Brown clay & soft sandstone				62	68	
Sand & gravel				68	92	
Brown clay				92	99	
Sand & gravel				99	111	
Gray clay				111	113	
(Use a second sheet if needed)						
18. Elevation:		19. Remarks: 176.3				
Topography: ___ Hill ___ Slope ___ Upland ___ Valley		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name Address Great Bend, KS 67530 License No. Signed [Signature] Date 4-27-77 Authorized representative				
6. Bore hole dia. 24 in. Completion date 4-26-77 Well depth 113 ft.				7. ___ Cable tool ___ Rotary ___ Driven ___ Dug ___ Hollow rod ___ Jetted ___ Bored ☒ Reverse rotary		
8. Use: ___ Domestic ___ Public supply ___ Industry ☒ Irrigation ___ Air conditioning ___ Stock ___ Lawn ___ Oil field water ___ Other				9. Casing: Material steel Height Above or below Threaded ___ Welded ☒ Surface 12 in. RMP ___ PVC ___ Weight 30.3 lbs./ft. Dia. 16 in. to 45 ft. depth Wall Thickness: inches or Dia. ___ in. to ___ ft. depth gage No. 7 ga.		
10. Screen: Manufacturer's name Doerr Type Double-slot Dia. 16" Slot gauze 1/8 Length 68' Set between 45 ft. and 113 ft. Gravel pack? yes Size range of material 3/8-200				11. Static water level: ___ mo./day/yr. 18' 6" ft. below land surface Date 2-17-77		
12. Pumping level below land surfaces: N/C ___ ft. after ___ hrs. pumping ___ g.p.m. ___ ft. after ___ hrs. pumping ___ g.p.m. Estimated maximum yield ___ g.p.m.				13. Water sample submitted: ___ mo./day/yr. ___ Yes ☒ No Date		
14. Well head completion: ___ Pitless adapter 12 Inches above grade				15. Well grouted? yes With: ☒ Neat cement ___ Bentonite ___ Concrete Depth: From 0 ft. to 10 ft.		
16. Nearest source of possible contamination: FIELD ft. ___ Direction ___ Type ___ Well disinfected upon completion? ___ Yes ☒ No				17. Pump: ___ Not installed Manufacturer's name Peerless Pump Model number 12MB-4 HP 75 Volt 160 Length of drop pipe 60 ft. capacity 900 g.p.m. Type: ___ Submersible ☒ Turbine ___ Jet ___ Reciprocating ___ Centrifugal ___ Other		