

1. Location of well:	County Barton	Fraction 1/4 1/4 C NW 1/4	Section number 26	Township number T 20	Range number S 13 R 13	
2. Distance and direction from nearest town or city:	45.1 E		3. Owner of well: George Engleman			
Street address of well location if in city:	Great Bend, KS.		R.R. or street: R2 City, state, zip code: Great Bend KS			
4. Locate with "X" in section below:	Sketch map:		6. Bore hole dia. 30 in. Completion date 12-1-76 Well depth 62 ft.			
			7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary			
			8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other			
5. Type and color of material			From	To	9. Casing: Material Steel Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight ☐ lbs./ft. Dia. 16 in. to 42 ft. depth Wall Thickness: ☐ inches or Dia. ☐ in. to ☐ ft. depth gage No. 3/16"	
Top Soil-Clay			0	12	10. Screen: Manufacturer's name Doerr Type Steel Dia. 16" Slot/gauze 1/8" Length 20' Set between 42 ft. and 62 ft. Gravel pack? ☒ Size range of material 1/8"/3/4"	
Sand			12	30	11. Static water level: ☐ ft. after ☐ hrs. pumping ☐ g.p.m. 19 ft. below land surface Date 12-1-76	
Sand-clay			30	35	12. Pumping level below land surfaces: 42 ft. after 4 hrs. pumping 1000 g.p.m. Estimated maximum yield 1200 g.p.m.	
Sand-Gravel			35	62	13. Water sample submitted: ☐ Yes ☒ No Date 10-11-76	
					14. Well head completion: ☐ Pitless adapter 24 inches above grade	
					15. Well grouted? ☐ With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.	
					16. Nearest source of possible contamination: None ft. ☐ Direction ☐ Type ☐ Well disinfected upon completion? ☐ Yes ☐ No	
					17. Pump: ☐ Not installed Manufacturer's name Goulds Model number 3125 HP 50 Volts 460 Length of drop pipe 50 ft. capacity 900 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
18. Elevation:			19. Remarks:			
Topography: ☐ Hill ☐ Slope ☒ Upland ☐ Valley			19.5			
			20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. 186 Kelly's Water Well Ser. Business name R2, Great Bend, KS License No. 186 Address Kelly's Pines Signed Kelly Pines Date 12-1-76 Authorized representative			