

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Barton	Fraction 1/4 1/4 CSW 1/4	Section number 36	Township number T 20 S	Range number R 13 E (W)		
2. Distance and direction from nearest town or city: 8 1/2 miles Southeast of Great Bend, KS Street address of well location if in city:			3. Owner of well: Marvin Johnstons, Jr. R.R. or street: 2015 Forest City, state, zip code: Great Bend, KS 67530					
4. Locate with "X" in section below: N W E S 1 Mile 1 Mile			Sketch map: 		6. Bore hole dia. 24 in. Completion date 8-26-76 Well depth 120 ft.			
5. Type and color of material			From	To	7. Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary			
			top soil & sandy clay		0	4	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other	
			sandy clay		4	9	9. Casing: Material steel Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight 30.3 lbs./ft.	
			white clay		9	18	Dia. 16 in. to 60 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 7 ga.	
			yellow clay		18	21	10. Screen: Manufacturer's name Brown Type Double-slot Dia. 16" Slot gauze 1/8" Length 60" Set between 60 ft. and 120 ft. ☐ ft. and ☐ ft.	
			sand		21	22	Gravel pack? yes Size range of material 3/8-200	
			white clay		22	28	11. Static water level: ☐ mo./day/yr. 16'2" ft. below land surface Date 8-17-76	
			yellow clay		28	30	12. Pumping level below land surfaces: N/C ☐ ft. after ☐ hrs. pumping ☐ g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield ☐ g.p.m.	
			sand & gravel		30	51	13. Water sample submitted: ☐ mo./day/yr. ☐ Yes ☒ No Date ☐	
			yellow & brown clay		51	53	14. Well head completion: ☐ Pitless adapter 12 Inches above grade	
			blue clay		53	58	15. Well grouted? yes With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.	
			soft clay & sand streaks		58	61	16. Nearest source of possible contamination: ft. ☐ Direction ☐ Type ☐ NONE KNOWN	
			sand		61	63	Well disinfected upon completion? ☐ Yes ☒ No	
			sand & gravel		63	97	17. Pump: ☐ Not installed Manufacturer's name FMC Corp./Peerless Model number 12MB-4 HP 60 Volts 460 Length of drop pipe 60 ft. capacity 900 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
			brown clay		97	106	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Equip., Inc. 185 Business name License No. Address Great Bend, KS 67530 Signed [Signature] Date 8-27-76 Authorized representative	
sand & gravel		106	115					
sandy clay & sand (Use a second sheet if needed)		115	120					
18. Elevation: Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley		19. Remarks: 1863						