


1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: Barton		SE 1/4 NE 1/4 NE 1/4	16	T 20 S	R 13 E W
Distance and direction from nearest town or city street address of well if located within city? XXXXXXXXXX , Approx. 2 miles South of Great Bend, KS					
2 WATER WELL OWNER:		Mid States Sales & Service			
RR#, St. Address, Box # :		700 East 10th		Board of Agriculture, Division of Water Resources	
City, State, ZIP Code :		Great Bend, KS 67530		Application Number: not required	
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 71 ft. ELEVATION: unknown			
N 1 Mile W E S 		Depth(s) Groundwater Encountered 1. 16 ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL 16 ft. below land surface measured on mo/day/yr 7/30/81			
		Pump test data: Well water was not ck'd ft. after hours pumping gpm			
		Est. Yield gpm: Well water was ft. after hours pumping gpm			
		Bore Hole Diameter 9 in. to 71 ft., and in. to ft.			
5 TYPE OF BLANK CASING USED:		CASING JOINTS: Glued XX Clamped			
1 Steel		3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below)	Welded
2 PVC		4 ABS	7 Fiberglass		Threaded
Blank casing diameter 5 in. to 61 ft. Dia in. to ft. Dia in. to ft.					
Casing height above land surface 12 in., weight 1.5 lbs./ft. Wall thickness or gauge No. 200					
TYPE OF SCREEN OR PERFORATION MATERIAL:		7 PVC 10 Asbestos-cement			
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify)					
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)					
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped 8 Saw cut 11 None (open hole)			
1 Continuous slot 3 Mill slot 6 Wire wrapped 9 Drilled holes					
2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)					
SCREEN-PERFORATED INTERVALS: From 61 ft. to 71 ft. From ft. to ft. From ft. to ft. From ft. to ft.					
GRAVEL PACK INTERVALS: From 51 ft. to 71 ft. From ft. to ft. From ft. to ft. From ft. to ft.					
Annular fill From 10 ft. to 43 ft. From ft. to ft. From ft. to ft. From ft. to ft.					
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other					
Grout Intervals: From 0 ft. to 10 ft. From 43 ft. to 51 ft. From ft. to ft. From ft. to ft.					
What is the nearest source of possible contamination:		10 Livestock pens 14 Abandoned water well			
1 Septic tank 4 Lateral lines 7 Pit privy 11 Fuel storage 15 Oil well/Gas well					
2 Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 16 Other (specify below)					
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage Field					
Direction from well? all		How many feet?			
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
0	11	Fine sand & topsoil			
11	25	Fine sand & very fine sand & gravel			
25	29	Very soft tan clay			
29	55	Fine sand & very fine sand & gravel w/ thin clay streaks			
55	71	Sand & gravel, med. to fine			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 7-30-81 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 185. This Water Well Record was completed on (mo/day/yr) 9-4-81 under the business name of CLARKE WELL & EQ., INC. by (signature) [Signature]					
INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.					