


1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: Barton		$\frac{1}{4}$ C $\frac{1}{4}$ SE $\frac{1}{4}$	23	T 20 S	R 13 E/W
Distance and direction from nearest town or city street address of well if located within city? 4 1/8 South 1 3/4 East north side of road from Great Bend					
2 WATER WELL OWNER: Ray Schulz					
RR#, St. Address, Box #: 3030 Broadway					
City, State, ZIP Code: Great Bend, Ks. 67530					
Board of Agriculture, Division of Water Resources					
Application Number: 34,747					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 60 ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL 12 ft. below land surface measured on mo/day/yr 7-7-81			
		Pump test data: Well water was 46 ft. after 1 hours pumping 60.0 gpm			
		Est. Yield 650 gpm: Well water was 48 ft. after 1 1/2 hours pumping 65.0 gpm			
		Bore Hole Diameter 29 in. to 60 ft. and in. to ft.			
		WELL WATER TO BE USED AS:			
		5 Public water supply 8 Air conditioning 11 Injection well			
		1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)			
		2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well			
		Was a chemical/bacteriological sample submitted to Department? Yes No X; If yes, mo/day/yr sample was submitted			
		Water Well Disinfected? Yes HTH No			
5 TYPE OF BLANK CASING USED:		CASING JOINTS: Glued Clamped			
1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile		Welded X Threaded			
2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below)					
7 Fiberglass					
Blank casing diameter 16 in. to 40 ft. Dia in. to ft. Dia in. to ft.					
Casing height above land surface 18 in. weight lbs./ft. Wall thickness or gauge No. 7					
TYPE OF SCREEN OR PERFORATION MATERIAL:		7 PVC 10 Asbestos-cement			
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify)					
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)					
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped 8 Saw cut 11 None (open hole)			
1 Continuous slot 3 Mill slot 6 Wire wrapped 9 Drilled holes					
2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)					
SCREEN-PERFORATED INTERVALS: From 40 ft. to 60 ft. From ft. to ft.					
GRAVEL PACK INTERVALS: From 10 ft. to 95 ft. From ft. to ft.					
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other					
Grout Intervals: From 0 ft. to 10 ft. From ft. to ft. From ft. to ft.					
What is the nearest source of possible contamination:		10 Livestock pens 14 Abandoned water well			
1 Septic tank 4 Lateral lines 7 Pit privy 11 Fuel storage 15 Oil well/Gas well					
2 Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 16 Other (specify below)					
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage					
Direction from well? West		How many feet? 3/4 mile			
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
0	2	Top soil			
2	21	Sandy brown clay			
21	29	Brown and gray clay			
29	31	Fine sand			
31	60	Sand and gravel-medium			
60	84	Gray clay			
84	88	Sand			
88	94	Sandy clay			
94	95	Hard sand rock			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 7-24-81 and this record is true to the best of my knowledge and belief. Kansas					
Water Well Contractor's License No. 134 This Water Well Record was completed on (mo/day/yr) 8-26-81					
under the business name of Rosencrantz-Bemis Ent. by (signature) Xora Dodson					
INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.					