

WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.

20120061

1 LOCATION OF WATER WELL: County: Barton		Fraction ¼ NE ¼ NW ¼ SW ¼	Section Number 19	Township No. T 20 S	Range Number R 13 ☐ E ☒ W																																																																		
Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☐ . 4S, 2W of Great Bend, KS			Global Positioning System (GPS) information: Latitude: (in decimal degrees) Longitude: (in decimal degrees) Elevation: Datum: ☐ WGS 84, ☐ NAD 83, ☐ NAD 27 Collection Method: ☐ GPS unit (Make/Model:) ☐ Digital Map/Photo, ☐ Topographic Map, ☐ Land Survey Est. Accuracy: ☐ <3 m, ☐ 3-5 m, ☐ 5-15 m, ☐ >15 m																																																																				
2 WATER WELL OWNER: David Panning RR#, Street Address, Box #: 152 SW 50 Road City, State, ZIP Code : Great Bend, KS 67530																																																																							
3 LOCATE WELL WITH AN "X" IN SECTION BOX: N <table border="1" style="width:100%; text-align: center; border-collapse: collapse;"> <tr><td> </td><td> </td><td> </td></tr> <tr><td>-- NW --</td><td>X</td><td>-- NE --</td></tr> <tr><td>-- SW --</td><td> </td><td>-- SE --</td></tr> <tr><td> </td><td> </td><td> </td></tr> </table> S -----1 mile-----					-- NW --	X	-- NE --	-- SW --		-- SE --				4 DEPTH OF COMPLETED WELL 95 ft. Depth(s) Groundwater Encountered (1) 20 ft. (2) ft. (3) ft. WELL'S STATIC WATER LEVEL 20 ft. below land surface measured on mo/day/yr. 02/07/12 Pump test data: Well water was ft. after hours pumping gpm EST. YIELD 80 gpm. Well water was ft. after hours pumping gpm Bore Hole Diameter in. to ft., and in. to ft. WELL WATER TO BE USED AS: ☐ Public water supply ☐ Geothermal ☐ Injection well ☐ Domestic ☐ Feedlot ☒ Oil field water supply ☐ Dewatering ☐ Other (Specify below) ☐ Irrigation ☐ Industrial ☐ Domestic-lawn & garden ☐ Monitoring well Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No If yes, mo/day/yr sample was submitted Water well disinfected? ☒ Yes ☐ No																																																									
-- NW --	X	-- NE --																																																																					
-- SW --		-- SE --																																																																					
5 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other CASING JOINTS: ☒ Glued ☐ Clamped ☐ Welded ☐ Threaded Casing diameter 5 in. to 7.5 ft., Diameter in. to ft., Diameter in. to ft. Casing height above land surface 12 in., Weight 2.8 lbs./ft., Wall thickness or gauge No. Sch. 40 TYPE OF SCREEN OR PERFORATION MATERIAL: ☐ Steel ☐ Stainless Steel ☒ PVC ☐ Other (Specify) ☐ Brass ☐ Galvanized Steel ☐ None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: ☐ Continuous slot ☐ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole) ☐ Louvered shutter ☐ Key punched ☐ Wire wrapped ☒ Saw cut ☐ Other (specify) SCREEN-PERFORATED INTERVALS: From 7.5 ft. to 9.5 ft., From ft. to ft. GRAVEL PACK INTERVALS: From 20 ft. to 56 ft., From 61 ft. to 95 ft. From ft. to ft., From ft. to ft.																																																																							
6 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☐ Other Grout Intervals: From 0 ft. to 20 ft., From 56 ft. to ft., From ft. to ft. What is the nearest source of possible contamination: ☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☐ Other (specify below) ☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☐ Fuel storage ☐ Abandoned water well ☐ Watertight sewer lines ☐ Seepage pit ☐ Feedyard ☐ Fertilizer storage ☒ Oil well/gas well Direction from well East Distance from well 120 <table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>FROM</th> <th>TO</th> <th>LITHOLOGIC LOG</th> <th>FROM</th> <th>TO</th> <th>LITHO. LOG (cont.) or PLUGGING INTERVALS</th> </tr> </thead> <tbody> <tr><td>0</td><td>2</td><td>top soil</td><td></td><td></td><td></td></tr> <tr><td>2</td><td>21</td><td>sandy clay</td><td></td><td></td><td>Panning 1-19</td></tr> <tr><td>21</td><td>35</td><td>sand and gravel</td><td></td><td></td><td></td></tr> <tr><td>35</td><td>56</td><td>clay with sand and gravel streaks</td><td></td><td></td><td>Sterling Drilling Company</td></tr> <tr><td>56</td><td>74</td><td>clay</td><td></td><td></td><td>P O Box 1006</td></tr> <tr><td>74</td><td>95</td><td>sand and gravel</td><td></td><td></td><td>Pratt, KS 67124</td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> </tbody> </table>						FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS	0	2	top soil				2	21	sandy clay			Panning 1-19	21	35	sand and gravel				35	56	clay with sand and gravel streaks			Sterling Drilling Company	56	74	clay			P O Box 1006	74	95	sand and gravel			Pratt, KS 67124																								
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS																																																																		
0	2	top soil																																																																					
2	21	sandy clay			Panning 1-19																																																																		
21	35	sand and gravel																																																																					
35	56	clay with sand and gravel streaks			Sterling Drilling Company																																																																		
56	74	clay			P O Box 1006																																																																		
74	95	sand and gravel			Pratt, KS 67124																																																																		
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) 02/07/12 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 186 This Water Well Record was completed on (mo/day/year) 02/08/12 under the business name of Kelly's Water Well Service, Inc. by (signature) <i>Kelly's Water Well Service, Inc.</i>																																																																							
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5524. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at http://www.kdheks.gov/waterwell/index.html .																																																																							