

WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.

30605

1 LOCATION OF WATER WELL: County: Barton		Fraction 1/4 NE 1/4 SW 1/4 NE 1/4		Section Number 21		Township No. T 20 S		Range Number R 13 ☐ E ☒ W																																																													
Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☐ Approximately 4.5 miles south of Great Bend.				Global Positioning System (GPS) information: Latitude: 38.29983 (in decimal degrees) Longitude: -98.760808 (in decimal degrees) Elevation: Unknown Datum: ☐ WGS 84, ☒ NAD 83, ☐ NAD 27 Collection Method: ☒ GPS unit (Make/Model: WAAS) ☐ Digital Map/Photo, ☐ Topographic Map, ☐ Land Survey Est. Accuracy: ☐ <3 m, ☒ 3-5 m, ☐ 5-15 m, ☐ >15 m																																																																	
2 WATER WELL OWNER: Esfeld-Meier Trust RR#, Street Address, Box #: 1212 McKinley City, State, ZIP Code : Great Bend, KS 67530																																																																					
3 LOCATE WELL WITH AN "X" IN SECTION BOX: N W <table border="1" style="display: inline-table; width: 100px; height: 100px; vertical-align: middle;"> <tr><td>--NW--</td><td>--NE--</td></tr> <tr><td>--SW--</td><td>--SE--</td></tr> </table> E S 1 mile		--NW--	--NE--	--SW--	--SE--	4 DEPTH OF COMPLETED WELL 108 ft. Depth(s) Groundwater Encountered (1) _____ ft. (2) _____ ft. (3) _____ ft. WELL'S STATIC WATER LEVEL 29 ft. below land surface measured on mo/day/yr: 06/07/13 Pump test data: Well water was not checked ft. after _____ hours pumping _____ gpm EST. YIELD _____ gpm. Well water was _____ ft. after _____ hours pumping _____ gpm Bore Hole Diameter 24 in. to 108 ft., and _____ in. to _____ ft. WELL WATER TO BE USED AS: ☐ Public water supply ☐ Geothermal ☐ Injection well ☐ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☐ Other (Specify below) ☒ Irrigation ☐ Industrial ☐ Domestic-lawn & garden ☐ Monitoring well Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No If yes, mo/day/yr sample was submitted _____ Water well disinfected? ☒ Yes ☐ No																																																															
--NW--	--NE--																																																																				
--SW--	--SE--																																																																				
5 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other _____ CASING JOINTS: ☒ Glued ☐ Clamped ☐ Welded ☐ Threaded Casing diameter 16 in. to 64 ft., Diameter 16 in. to 99 ft., Diameter _____ in. to _____ ft. Casing height above land surface 12 in., Weight 19.75 lbs./ft., Wall thickness or gauge No. .616 TYPE OF SCREEN OR PERFORATION MATERIAL: ☐ Steel ☒ Stainless Steel ☒ PVC ☐ Other (Specify) _____ ☐ Brass ☐ Galvanized Steel ☐ None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: ☐ Continuous slot ☒ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole) ☐ Louvered shutter ☐ Key punched ☒ Wire wrapped ☐ Saw cut ☐ Other (specify) _____ SCREEN-PERFORATED INTERVALS: From 64 ft. to 75 ft., From 75 ft. to 89 ft. From 99 ft. to 107 ft., From _____ ft. to _____ ft. GRAVEL PACK INTERVALS: From 22 ft. to 108 ft., From _____ ft. to _____ ft. From _____ ft. to _____ ft., From _____ ft. to _____ ft.																																																																					
6 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☐ Other _____ Grout Intervals: From 2 ft. to 22 ft., From _____ ft. to _____ ft., From _____ ft. to _____ ft. What is the nearest source of possible contamination: ☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☒ Other (specify below) ☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☐ Fuel storage ☐ Abandoned water well ☐ Watertight sewer lines ☐ Seepage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well Direction from well _____ Distance from well _____ None Known																																																																					
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>FROM</th> <th>TO</th> <th>LITHOLOGIC LOG</th> <th>FROM</th> <th>TO</th> <th>LITHO. LOG (cont.) or PLUGGING INTERVALS</th> </tr> </thead> <tbody> <tr><td>0</td><td>21</td><td>Sandy, clay, brown</td><td></td><td></td><td></td></tr> <tr><td>21</td><td>29</td><td>Sand, coarse to fine</td><td></td><td></td><td></td></tr> <tr><td>29</td><td>36</td><td>Clay, brown, with sand, coarse to fine</td><td></td><td></td><td></td></tr> <tr><td>36</td><td>54</td><td>Sand & gravel, fine</td><td></td><td></td><td></td></tr> <tr><td>54</td><td>89</td><td>Sand & gravel, coarse to fine</td><td></td><td></td><td></td></tr> <tr><td>89</td><td>99</td><td>Clay, brown, sandy</td><td></td><td></td><td></td></tr> <tr><td>99</td><td>102</td><td>Sand, coarse to fine</td><td></td><td></td><td></td></tr> <tr><td>102</td><td>107</td><td>Clay, brown & gravel, medium</td><td></td><td></td><td></td></tr> <tr><td>107</td><td>108</td><td>Clay, tan, yellow</td><td></td><td></td><td></td></tr> </tbody> </table>										FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS	0	21	Sandy, clay, brown				21	29	Sand, coarse to fine				29	36	Clay, brown, with sand, coarse to fine				36	54	Sand & gravel, fine				54	89	Sand & gravel, coarse to fine				89	99	Clay, brown, sandy				99	102	Sand, coarse to fine				102	107	Clay, brown & gravel, medium				107	108	Clay, tan, yellow			
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS																																																																
0	21	Sandy, clay, brown																																																																			
21	29	Sand, coarse to fine																																																																			
29	36	Clay, brown, with sand, coarse to fine																																																																			
36	54	Sand & gravel, fine																																																																			
54	89	Sand & gravel, coarse to fine																																																																			
89	99	Clay, brown, sandy																																																																			
99	102	Sand, coarse to fine																																																																			
102	107	Clay, brown & gravel, medium																																																																			
107	108	Clay, tan, yellow																																																																			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) 06/07/13 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 185 This Water Well Record was completed on (mo/day/year) 06/19/13 under the business name of Clarke Well & Equipment, Inc. by (signature) _____																																																																					
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at http://www.kdheks.gov/waterwell/index.html .																																																																					