

1 LOCATION OF WATER WELL:		Fraction	Section Number		Township Number	Range Number	
County: Barton		NE $\frac{1}{4}$ NW $\frac{1}{4}$ NE $\frac{1}{4}$	3		T 20 S	R 14 EW	
Distance and direction from nearest town or city street address of well if located within city?							
Airport Road, Great Bend, Kansas							
2 WATER WELL OWNER:		City of Great Bend - Great Bend Municipal Airport			Board of Agriculture, Division of Water Resources		
RR#, St. Address, Box # :		P.O. Box 1168			Application Number:		
City, State, ZIP Code :		Great Bend, Ks. 67530					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 20 ft. ELEVATION: NA					
1 Mile N W E S		Depth(s) Groundwater Encountered 1. 13 ft. 2. _____ ft. 3. _____ ft.					
		WELL'S STATIC WATER LEVEL 13.2 ft. below land surface measured on mo/day/yr 03-02-94					
		Pump test data: Well water was _____ ft. after _____ hours pumping _____ gpm					
		Est. Yield _____ gpm: Well water was _____ ft. after _____ hours pumping _____ gpm					
		Bore Hole Diameter. 7.5/8 in. to 20 ft., and in. to ft.					
TYPE OF BLANK CASING USED:		CASING JOINTS: Glued _____ Clamped _____					
1 Steel 3 RMP (SR)		5 Wrought iron 8 Concrete tile Welded _____					
(2) PVC 4 ABS		6 Asbestos-Cement 9 Other (specify below) Threaded. X					
Blank casing diameter 2 in. to 10 ft., Dia. in. to ft., Dia. in. to ft.		7 Fiberglass					
Casing height above land surface +30 in., weight lbs./ft. Wall thickness or gauge No. sch. 40		TYPE OF SCREEN OR PERFORATION MATERIAL:					
1 Steel 3 Stainless steel 5 Fiberglass		(7) PVC 10 Asbestos-cement					
2 Brass 4 Galvanized steel 6 Concrete tile		8 RMP (SR) 11 Other (specify)					
SCREEN OR PERFORATION OPENINGS ARE:		12 None used (open hole)					
1 Continuous slot (3) Mill slot		8 Saw cut 11 None (open hole)					
2 Louvered shutter 4 Key punched		9 Drilled holes					
SCREEN-PERFORATED INTERVALS: From 10 ft. to 20 ft., From ft. to ft.		10 Other (specify)					
GRAVEL PACK INTERVALS: From 8 ft. to 20 ft., From ft. to ft.		From ft. to ft., From ft. to ft.					
6 GROUT MATERIAL:		1 Neat cement (2) Cement grout (3) Bentonite 4 Other					
Grout Intervals: From 0 ft. to 6 ft., From 6 ft. to 8 ft., From ft. to ft.		What is the nearest source of possible contamination:					
1 Septic tank 4 Lateral lines 7 Pit privy		10 Livestock pens 14 Abandoned water well					
2 Sewer lines 5 Cess pool 8 Sewage lagoon		(11) Fuel storage 15 Oil well/Gas well					
3 Watertight sewer lines 6 Seepage pit 9 Feedyard		12 Fertilizer storage 16 Other (specify below)					
Direction from well? south		13 Insecticide storage					
		How many feet? 2					
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS		
0	5.5	clay, mod-dk brn, sl sandy, sl-mod silty, tr calic, moist					
5.5	7	snd, lt-mod brn, f-v c w/tr grvl, thin cl seams, p srtcd, damp					
7	14	snd, lt brn, f-v c w/f-m grvl, p srtcd, damp					
14	20	snd, dk gry, f-v c w/f-m grvl, p srtcd, sat					
MW1-above ground cover							
Site ID 00023430							
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 03-02-94 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 527 This Water Well Record was completed on (mo/day/yr) 04-01-94 under the business name of GeoCore Services, Inc. by (signature) <i>[Signature]</i>							