

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

County Barton	Fraction 1/4 c x 1/4 nw 1/4	Section number 13	Township number 20 T S R	Range number 14 E W	
2. Distance and direction from nearest town or city: 3-S 3/4-W from Great Bend, Ks. Street address of well location if in city:		3. Owner of well: Harold Titus R.R. or street: Box 1010 City, state, zip code: Great Bend, Kansas 67530			
4. Locate with "X" in section below: N W E S 1 Mile		Sketch map: 6. Bore hole dia. .29 in. Completion date _____ Well depth 95 ft. 6-5-79 7. Cable tool ☒ Rotary Driven Dug Hollow rod Jetted Bored Reverse rotary 8. Use: Domestic Public supply Industry ☒ Irrigation Air conditioning Stock Lawn Oil field water Other 9. Casing: Material steel Height: Above or below ground _____ Threaded Welded Surface 24 in. RMP PVC Weight _____ lbs./ft. Dia. 16 in. to 95 ft. depth Wall Thickness: inches or Dia. _____ in. to _____ ft. depth gage No. 7			
5. Type and color of material		From	To	10. Screen: Manufacturer's name _____ Boerrs Type steel Dia. _____ Slot/wire 3/16 Length 40 Set between 95 ft. and 55 ft. Gravel pack? ☒ Size range of material 2 3/4 3/8	
top soil		0	3	11. Static water level: _____ mo./day/yr. 15 ft. below land surface Date 5-29-79	
brown & gray clay		3	8	12. Pumping level below land surfaces: na _____ ft. after _____ hrs. pumping _____ g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield _____ g.p.m.	
sand & gravel clean coarse loose		8	35	13. Water sample submitted: _____ mo./day/yr. ☒ Yes _____ No Date 5-29-79	
brown clay		35	36	14. Well head completion: _____ Inches above grade Pitless adapter _____	
sand & gravel clean coarse loose		36	63	15. Well grouted? ☒ With: ☒ Neat cement _____ Bentonite _____ Concrete _____ Depth: From 0 ft. to 10 ft.	
brown clay		63	68	16. Nearest source of possible contamination: _____ ft. 800 Direction se Type septic Well disinfected upon completion? ☒ Yes _____ No	
sand & gravel		68	71	17. Pump: _____ Not installed Manufacturer's name W.L.R. Model number 5-10CH HP 40 Volts _____ Length of drop pipe 60 ft. capacity 1000 g.p.m. Type: _____ Submersible ☒ Turbine Jet Reciprocating Centrifugal Other	
brown & white clay		71	77		
sand & gravel		77	94		
clay w/little sand mixed.		94	105		
(Use a second sheet if needed)					
18. Elevation:	19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Rosencrantz-Bemis 134 Business name License No. Address Great Bend, Kansas 67530 Signed Sandy Kulgoe Date 6-15- Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5