

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Barton	Fraction se 1/4 nw 1/4 se 1/4	Section number 13	Township number T 20 S R 14 E 0	Range number				
2. Distance and direction from nearest town or city: 4-E 1/4-M of M Dundee, Ks. Street address of well location if in city:			3. Owner of well: Harold Titus R.R. or street: Box 1010 City, state, zip code: Great Bend, Kansas 67530						
4. Locate with "X" in section below: N 1 Mile W <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 20px; height: 20px; text-align: center;">NW</td><td style="width: 20px; height: 20px; text-align: center;">NE</td></tr><tr><td style="width: 20px; height: 20px; text-align: center;">SW</td><td style="width: 20px; height: 20px; text-align: center;">SE</td></tr></table> E S 1 Mile			NW	NE	SW	SE	Sketch map: 1 Mile		
NW	NE								
SW	SE								
5. Type and color of material			From	To	6. Bore hole dia. 29 in. Completion date 2-6-76 Well depth 128 ft.				
top soil			0	1	7. ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary				
clay			1	15	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other				
sand & gravel			15	33	9. Casing: Material steel Height: Above or below XXXX Threaded ☐ Welded ☐ Surface 18 in. RMP ☐ PVC ☐ Weight ☐ lbs./ft. Dia. 16 in. to 128 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 7				
clay			33	35	10. Screen: Manufacturer's name Doerrs Type steel Dia. ☐ Slot/ size 3/16 Length 20 Set between 108 ft. and 128 ft. ☐ ft. and ☐ ft. Gravel pack? ☒ Size range of material 3/4 3/8				
sand & gravel			35	43	11. Static water level: ☐ mo./day/yr. 15 ft. below land surface Date 12-13-75				
clay			43	44	12. Pumping level below land surfaces: 49 ft. after 1 hrs. pumping 800 g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield 1400+ g.p.m.				
gravel			44	68	13. Water sample submitted: ☐ mo./day/yr. ☒ Yes ☐ No Date 12-13-75				
clay			68	73	14. Well head completion: ☐ Pitless adapter ☐ Inches above grade				
fine sand			73	75	15. Well grouted? ☒ With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.				
clay			75	83	16. Nearest source of possible contamination: ft. 5-M Direction south Type septic Well disinfected upon completion? ☒ Yes ☐ No				
sand & clay			83	93	17. Pump: Not installed Manufacturer's name W.L.R. Model number 6-100M HP 30 Volts 460 Length of drop pipe 70 ft. capacity 800 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other				
clay			93	100	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Rosencrantz-Bemis 134 Business name License No. Address Great Bend, Kansas 67530 Signed L. Pilgore Date 6-19-79 Authorized representative				
sand & clay			100	107					
good sand & gravel			107	125					
hard clay			125	128					
(Use a second sheet if needed)									
18. Elevation:	19. Remarks: 1782								
Topography: ☐ Hill ☐ Slope ☒ Upland ☐ Valley									

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5

20 14 13 SE NW SE
1/4 1/4 1/4