


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County <u>Barton</u>	Fraction <u>1/4</u> <u>1/4 CNW 1/4</u>	Section number <u>17</u>	Township number T <u>20</u> S	Range number R <u>14</u> E/W
2. Distance and direction from nearest town or city: <u>1/2 NW</u> Street address of well location if in city: <u>Dundee, KS</u>			3. Owner of well: <u>Roland Schmidt</u> R.R. or street: <u>R1 Great Bend, KS</u> City, state, zip code:			
4. Locate with "X" in section below: 			Sketch map:		6. Bore hole dia. <u>8</u> in. Completion date <u>8-21-76</u> Well depth <u>64</u> ft.	
5. Type and color of material			From		To	
			<u>Topsoil - Clay</u>		<u>0</u>	<u>20</u>
			<u>Sand</u>		<u>20</u>	<u>40</u>
			<u>Clay</u>		<u>40</u>	<u>45</u>
			<u>Sand - Gravel</u>		<u>45</u>	<u>60</u>
					7. ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary	
					8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other	
					9. Casing: Material ☐ Height: <u>Above</u> or below Threaded ☐ Welded ☐ Surface <u>12</u> in. RMP ☐ PVC ☒ Weight ☐ lbs./ft. Dia. <u>5</u> in. to <u>60</u> ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth Gauge No. <u>Sch 40</u>	
					10. Screen: Manufacturer's name <u>MPI</u> Type <u>PVC</u> Dia. <u>5</u> in. Slot/gauze <u>1/8</u> Length <u>10</u> Set between <u>50</u> ft. and <u>60</u> ft. <u>50</u> ft. and <u>60</u> ft. Gravel pack? ☒ Size range of material <u>1/8-3/4</u>	
					11. Static water level: <u>30</u> ft. below land surface Date <u>8-21-76</u> mo./day/yr.	
					12. Pumping level below land surfaces: <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u>35</u> g.p.m.	
					13. Water sample submitted: <u> </u> mo./day/yr. Yes ☒ No ☐ Date <u> </u>	
					14. Well head completion: <u> </u> Pitless adapter <u>12</u> Inches above grade	
					15. Well grouted? <u> </u> With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From <u>6</u> ft. to <u>10</u> ft.	
					16. Nearest source of possible contamination: ft. <u>60</u> Direction <u>N</u> Type <u>SEWER</u> Well disinfected upon completion? ☒ Yes ☐ No	
					17. Pump: ☒ Not installed Manufacturer's name <u> </u> Model number <u> </u> HP <u> </u> Volts <u> </u> Length of drop pipe <u> </u> ft. capacity <u> </u> g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
					(Use a second sheet if needed)	
18. Elevation: Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Kenny Water Well Ser. 186</u> Business name <u>R2 Great Bend, KS</u> License No. <u> </u> Address <u> </u> Signed <u>Kenny Price</u> Date <u>8-21-76</u> Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5